Coupled regional Earth System modeling in the Baltic Sea region

Matthias Gröger[1], Christian Dieterich[2][†], Jari Haapala[3], Ha Thi Minh Ho-Hagemann[4], Stefan Hagemann[4], Jaromir Jakacki,[5] Wilhelm May[6], H.E. Markus Meier[1,2], Paul. A. Miller[6,7], Anna Rutgersson[8], Lichuan Wu[8],

[1]Department of Physical Oceanography and Instrumentation, Leibniz Institute for Baltic Sea Research Warnemünde, Rostock, 18119, Germany
[2]Research and Development Department, Swedish Meteorological and Hydrological Institute, Norrköping, 601 76, Sweden
[3]Institute Finnish Meteorological Institute, Helsinki, Finland
[4]Institute of Coastal Systems - Analysis and Modeling, Helmholtz-Zentrum Geesthacht, Geesthacht, 21502 Germany
[5]Institute of Oceanology, Polish Academy of Sciences, Sopot, Poland
[6]Centre for Environmental and Climate Science, Lund, University, Lund, 223 62 Sweden
[7]Department of Physical Geography and Ecosystem Science, Lund University, Sweden
[8]Department of Earth Sciences, Uppsala University, Sweden

Correspondence to: Matthias Gröger (matthias.groeger@io-warnemuende.de)

[†]During the time in which this paper was prepared, shortly before acceptance, Christian Dieterich passed away (1964-2021). This sad event marked the end of the life of a distinguished oceanographer and climate scientist who made important contributions to the climate modeling of the Baltic Sea, North Sea and North Atlantic regions.

Abstract

Non-linear responses to externally forced climate change are known to dampen or amplify the local climate impact due to complex cross compartmental feedback loops in the earth system. These feedbacks are less well represented in traditional standalone atmosphere and ocean models on which many of today's regional climate assessments rely ~~on~~ (e.g. EuroCordex, NOSCCA, BACC II). This promotes the development of regional climate models for the Baltic Sea region by coupling different compartments of the earth system into more comprehensive models. Coupled models more realistically represent feedback loops than the information imposed into the region by using prescribed boundary conditions, and thus, permit a higher degree of freedom. In the past, several coupled model systems have been developed for Europe and the Baltic Sea region. This article reviews recent progress of model systems that allow two way communication between atmosphere and ocean models, models for the land surface including the terrestrial biosphere, as well as wave models at the air sea interface and hydrology models for water cycle closure. However, several processes that have so far mostly been realized by one way coupling such as marine biogeochemistry, nutrient cycling and atmospheric chemistry (e.g. aerosols) are not considered here.

Compared to uncoupled standalone models, coupled earth system models can modify mean near surface air temperatures locally up to several degrees compared to their standalone atmospheric counterparts using prescribed surface boundary conditions. Over open ocean areas, the representation of small scale oceanic processes such as vertical mixing, and sea ice dynamics appear essential to accurately resolve the air sea heat exchange in the Baltic Sea region and can only be provided by online coupled high resolution ocean models. In addition, the coupling of wave models at the ocean-atmosphere interface allows a more explicit formulation of small-scale to microphysical processes with local feedbacks to water temperature and large scale processes such as oceanic upwelling. Over land, important climate feedbacks arise from dynamical terrestrial vegetation changes as well as the implementation of land use scenarios and afforestation/deforestation that further alter surface albedo,

roughness length and evapotranspiration. Furthermore, a good representation of surface temperatures and roughness length over open sea and land areas is critical for the representation of climatic extremes like e.g. heavy precipitation, storms, or tropical nights, and appear to be sensitive to coupling.

For the present-day climate, many coupled atmosphere-ocean and atmosphere-land surface models demonstrate added value with respect to single climate variables in particular when low quality boundary data were used in the respective standalone model. This makes coupled models a prospective tool for downscaling climate change scenarios from global climate models because these models often have large biases on the regional scale. However, the coupling of hydrology models for closing the water cycle remains problematic as the accuracy of precipitation provided by the atmosphere models is in most cases insufficient to realistically simulate the runoff to the Baltic Sea without bias adjustments.

Many regional standalone ocean and atmosphere models are tuned to well represent present day climatologies rather than accurately simulate climate change. More research is necessary about how the regional climate sensitivity (e.g. the models' response to a given change in global mean temperature) is affected by coupling and how the spread is altered in multi-model and multi-scenario ensembles of coupled models compared to uncoupled ones.

1. Introduction

Climatic and environmental changes on regional scales are traditionally investigated using standalone models resolving processes specific for only one single environmental compartment (e.g. the terrestrial and marine biospheres, the hydrosphere, the atmosphere, the ocean, and the cryosphere, etc.). Many projections that served as a basis for the recent climate change assessments for the North Sea (NOSCCA, May et al., 2016, Schrum et al., 2016) and Baltic Sea (BACC II Author Team, 2015, Bøssing-Christensen et al., 2015; Bøssing-Christensen et al., 2021) or the Euro-Cordex region (Jacob et al., 2014) fall into the category of stand-alone ocean models or stand-alone atmosphere models whereas fewer assessments are based on coupled systems (Meier et al., 2015, and Meier et al., 2021). However, as environmental compartments interact with each other via mass, momentum and energy exchange, the interfaces and boundary layers between the compartments are of great importance.

The use of Earth System Models (ESM) that interactively couple atmospheric, marine and terrestrial energy, water and biogeochemical dynamics is becoming increasingly common practice in global climate assessments (e.g. IPCC 2013) and international coordinated protocols for climate simulations (e.g. the emission driven CMIP6-C4MIP, Jones et al., 2016). Their employment in regional climate change and impact studies (e.g. Döscher and Meier, 2004; Somot et al. 2008; Wramneby et al., 2010; Meier et al., 2011; Cabos et al., 2020; Sein et al., 2020a, Zhang et al., 2018; Soto-Navarro et al., 2020; Dieterich et al., 2019; Gröger et al., 2019; Gröger et al., 2021) is, however, still rare.

Climate change on regional scales can be much stronger than one would expect from external forcing such as greenhouse gases, solar radiation, etc. alone (e.g. Vogel et al., 2017; Stuecker et al., 2018). This is because the direct forcing can be strongly modulated by feedback processes that act to amplify or dampen the change in climate variables. Biophysical (e.g. albedo and evapotranspiration-mediated) feedbacks may significantly affect the interactions between the earth system compartments at the regional scale. Moreover, these feedbacks are affected by small-scale physiographic features, such as mountain ranges and coastline features, which are poorly captured by global ESMs when run at typically coarse grid resolution. Recognizing these issues, there is an emerging demand for regional ESMs suitable for application at higher grid resolutions over a regional domain, accounting for biophysical coupling between the atmosphere and surface. National - e.g. MERGE: http://www.merge.lu.se/about-merge - and international strategic programmes are now stepping up their efforts to meet this demand. The Baltic Earth program (www.baltic.earth), which brings together climate and environmental scientists around the Baltic Sea, emphasizes the importance of realistic coupled modeling to achieve an improved earth system understanding of the Baltic Sea region, with

100   "Multiple drivers for regional earth system changes" being one of the Grand Challenges addressed by the program (Reckermann et al., 2021).

Study area

Compared to other continents, Europe and the adjacent European marine sectors are extremely diverse
105   on especially small scales. Classifications based on precipitation, temperature distributions (Köppen, 1923) and other environmental factors (Metzger et al., 2005) distinguish between 5 and 18 different climate types ranging from polar climates in high mountainous areas and Iceland to temperate regions of humid or even dry nature (Figure 1, e.g. Kottek et al., 2006; Beck et al., 2018). By contrast, vast areas of comparably uniform environmental conditions that can be found on the world's bigger
110   cratonic continents are absent. Climatologically, the western part of Europe is influenced by the oceanic climate i.e. linked to the large heat content of the North Atlantic while the eastern part is of continental character with increased seasonality. Likewise, Europe is positioned between the fully polar climate in the North and subtropical climates to the South. Altogether, this makes Europe's climate fairly variable on small spatial scales and sensitive to perturbations in the large-scale
115   atmospheric circulation patterns as e.g. reflected in the strong impact of the North Atlantic Oscillation (NAO, Hurrel, 1995; Scaife et al., 2008; Rousi et al., 2020). Thus, the demand for modeling Europe's climate includes high resolution, as well as a comprehensive process description by respective coupled model components. This makes this region a challenging test case for high resolution earth system modeling.

ET, EF polar climates		**Dsa** snow climates, dry summer	
Dfc snow climates, fully humid, cool summer & cool winter		**Cf** warm temperate climates, fully humid	
Dfb snow climates, fully humid, warm summer		**Cs** warm temperate climate, dry summer	
Dfa snow climates, fully humid, hot summer		**BS** Arid climates, Cold Steppe/Desert	
		BW Arid climates, Hot Steppe/Desert	

120

Figure 1: Climate classification based on E-OBS monthly mean temperature and precipitation (Cornes et al., 2018). Classes are defined after Köppen (1923).

The Baltic Sea climate is influenced by temperate humid climate in the southwest and snow climate in the north and east (Fig. 1), with an enhanced seasonal cycle giving rise to highly variable
125   meteorological conditions related to predominant weather regimes over the region (Hertig and Jacobeit, 2014) ranging from severe storms, summer heat waves and winter cold air outbreaks (Smith and Sheridan, 2020) or prolonged dry periods in the southern part. Many of these phenomena are directly subject to local and regional thermal feedbacks between the atmosphere, the land and the ocean and thus require a realistic exchange of mass and energy as realized by interactively coupled
130   regional earth system models.

1.2 Towards earth system modeling of the Baltic Sea region

From a theoretical point of view the coupling of two or more interacting models to create a more comprehensive system implies that boundary processes formerly prescribed, parameterized or even

neglected are explicitly simulated. This removes observational constraints and/or empirically derived relationships on the model solutions and thus increases the model's degree of freedom. Consequently, coupled models can drift from observed conditions which makes their tuning more difficult but allows a more realistic interaction between models. Therefore, in their hindcast modes, standalone models can be expected to be closer to observations once prescribed boundary conditions are of good quality.

From the climate perspective, which envisages simulations over several decades or even centuries, the model should ideally be drift free to integrate over several millions of model time steps. Furthermore, in regard to future climate simulations the model boundary conditions like e.g. temperature are basically unknown and have to be derived in the standalone case from the output of available global climate models. Although advanced methods exist to make this data usable for high resolution models (e.g. Hay et al., 2007; Chen et al., 2016) there is evidence that in uncoupled ocean simulations the solution of the ocean models is too tightly controlled by the global model (Mathis et al., 2018).

Hence, earth system models are the prime tool for simulating cross-compartment feedback loops (Claussen, 2001; Giorgi and Gao, 2018; Heinze et al. 2019). In turn, such feedbacks play an important role for mediating the response of the earth climate to a given external forcing or perturbation. Consequently, the ability of ESMs to simulate such feedbacks is essential. However, the capability of coupled models to better represent cross-compartment feedbacks and more realistically model dynamical processes is often not adequately accounted for during model validation. By contrast, model validation usually aims to demonstrate the models' ability to represent mean climate. By their nature, climate models are tools to iteratively solve the change in a variable from a given time step to the next rather than predicting the variable at a given time. From this follows that the capability of a model to reproduce the transient behaviour such as interannual variability or long term trends is essential to estimate if a climate model can yield reliable answers to how changes in climate forcing will likely impact on climate variables. However, regional models are often validated more by how well they reproduce a given climatology of the present day climate rather than by how well they reproduce trends derived from the historical past (Kerr, 2013). As every compartment model has its own spectrum of internal space and time scales the inertia of the system increases when including slower components. This can become important especially when a decision about the size of the ocean model domain has to be taken. A larger extension to the open Atlantic or Arctic Ocean substantially increases the memory of the system which has consequences for the model spinup and the economic operation of the model system.

In the past decades several advancements in coupled modeling have led to a growing number of different regional climate models on the way to a fully comprehensive description of the earth system for many regions of the world e.g. the east coast of the U.S. (COAWST – Coastal Ocean-atmosphere-wave-sediment transport model, Warner et al., 2008; 2020). Recent reviews of global and regional earth system modeling have elaborated past and recent trends and summarized future challenges for further development (Schrum, 2017; Giorgi and Gao, 2018; Giorgi 2019; Heinze et al., 2019; Jacob et al., 2020). Realized stepstones on the roadmap towards coupled earth system modeling for the Baltic Sea region include coupled ocean sea ice − atmosphere models, coupled ocean wave and atmosphere wave models, coupled vegetation − atmosphere models and coupled ocean − atmosphere − hydrology models. This article aims at reviewing the latest developments, and describes the problems and benefits of using coupled models, with focus on the specific demands of the Baltic Sea region within Europe. Thus, the focus is mainly set on the main physical feedbacks as they emerge in 2-way coupled earth system components. Therefore, this article does not aim at being overarching as some important components are not considered such as biogeochemical nutrient cycling on land and in the Baltic Sea or atmospheric chemistry (e.g. effect of aerosols).

 ## 2. Current state of knowledge

2.1 Land surface-atmosphere coupling and modeling

Biophysical mechanisms

The Baltic Sea region's land surface and terrestrial ecosystems couple strongly to local climate, and biophysical interactions determine the exchanges of momentum, heat and water between the land and
185 the atmosphere and the spatiotemporal dynamics of the atmospheric boundary layer (ABL), including the wind speed, surface and air temperature, humidity and precipitation, and the atmospheric radiative balance.

Changes to the properties of the land surface and ecosystems, whether natural or anthropogenic, will lead to climate change through a number of well-established biogeochemical and biophysical
190 feedback mechanisms (IPCC 2019). The biogeochemical mechanisms include the release or uptake of greenhouse gases (primarily CO_2, though CH_4 and N_2O are of considerable importance in the Baltic Sea region; Gao et al. 2014) and the emissions of black carbon, aerosol precursors (e.g. biogenic volatile organic compounds; BVOC) and organic carbon aerosols that can alter the atmospheric composition, including cloud-condensation nuclei and the fraction of diffuse and global radiation (e.g.
195 Kulmala et al., 2014).

Important properties of the land surface include its albedo, its roughness, the species composition, the properties and phenology of green vegetation (e.g. leaf area index; LAI)) and plant physiology (e.g. leaf stomatal and canopy conductance). Local climate is altered as a result of changes to the shortwave and longwave radiation, the turbulent fluxes of sensible and latent heat (i.e.
200 evapotranspiration; ET)) and momentum (e.g. Bonan 2008; Anderson et al., 2011; Pielke et al., 2011; Mahmood et al. 2014; Ellison et al., 2017; IPCC 2019).

Forests typically have a lower surface albedo than grassland, pastures and cropland. Thus, deforestation tends to increase the albedo, while re- and afforestation have the opposite effect. Furthermore, coniferous forest albedo (0.05-0.15) is lower than deciduous forest albedo (0.15-0.20)
205 (Anderson et al. 2011; Bonan 2008). Hence, the species composition determines the net albedo in a given region. Since snow albedo ranges from 0.45-0.95 depending on age, history and mechanical disturbance, the albedo of the land surface in the Baltic Sea region is particularly sensitive to the duration and extent of snow cover, as well as the underlying vegetation type (Anderson et al. 2011). Re- or afforestation leads to a lower albedo in periods of snow cover, with greater net radiation at the
210 land surface, stronger sensible heat fluxes and a warming over the forested area as a result (Anderson et al. 2011).

Since trees are taller than grasses and crops, forested regions in the Baltic Sea region have greater roughness lengths and tend to couple more strongly to the atmosphere, creating more turbulence than grass-covered regions or cropland, with higher sensible and latent heat fluxes. An increase in the
215 surface roughness in association with re- or afforestation, increased rates of tree growth or altered forest management practices, can lead to stronger turbulent fluxes and strong turbulent mixing (Winckler et al. 2019).

Trees transpire more water than grass or crops as a result of their larger leaf area and deeper roots. Forests thus have higher evapotranspiration rates and latent heat fluxes than grasslands, though
220 irrigated croplands can also have high ET rates. Higher latent heat fluxes cool the surface and moisten the ABL. A decrease in the latent heat fluxes associated with deforestation tends to warm the surface and leads to higher sensible heat fluxes and a warming of the ABL. The ABL is also drier, which can lead to a reduction in precipitation.

Biophysical effects of land-use and land-cover changes on climate in the Baltic Sea region

A number of modeling studies have examined the influence of land-use and land-cover change (LULCC) on climate variables in northern European domains, including the Baltic Sea region. The standard approach (Gálos et al., 2012; Strandberg et al., 2014; Strandberg & Kjellström, 2019) is to alter the static land cover input to the coupled model and to compare simulations with an unchanged, control simulation. This approach does not permit two-way coupling in which local climate changes resulting from the perturbation subsequently alter land surface properties and vegetation characteristics.

Perugini et al. (2017; see also IPCC (2019) reviewed the published literature on the biophysical effects of anthropogenic land cover change on temperature and precipitation in boreal, temperate and tropical regions. 28 studies were included in their review, including three based on observations and 25 that were based on idealized regional and global climate model simulations designed to estimate the regional and global biophysical effects of complete deforestation or afforestation. To effect deforestation in their simulations, some authors replaced forest with grassland, and others replaced forest with bare soil. Modelled deforestation in boreal regions resulted in local cooling consistent with observations, but with a less consistent, slight cooling modelled in temperate regions in contrast to observations that indicate a slight warming in those zones.

Goa et al. (2014) used the REMO RCM to investigate the biophysical effects of extensive peatland drainage and afforestation in Finland during the 20th century. Simulations were made for a model domain centred on Finland, but covering a large part of the Baltic Sea region. The model grid had a horizontal resolution of 18 km with 27 vertical levels up to 25 km in the atmosphere.

Maps from the Finnish national forest inventory (FNFI) were used to compute changes to the fractional coverage of REMO's 10 land cover classes in Finland from the 1920s, when peatland drainage and forestation began, to the 2000s. Over this period, coniferous forest replaced large regions previously covered by peat bogs and mixed forest. Two 18-year (1979-1996) simulations were then made to compare the effect of the land cover change, driven with 6-hourly lateral boundary conditions from the ERA-Interim reanalysis data and identical land cover outside Finland.

Goa et al. (2014) found that the reduction in albedo associated with prescribed peatland forestation resulted in an increase of up to 0.43 K in 2 m air temperature in April, with the highest values being found over the most intensive forestation areas. In contrast, there was a slight cooling (< 0.1 K) over the growing season (May to October), associated with greater ET from coniferous forests.

Strandberg and Kjellström (2019) used the Rossby Centre RCM RCA4 (Strandberg et al. 2015; Kjellström et al. 2016) a successor to RCA3 (Samuelsson et al 2011) to investigate and attribute the climate impacts of maximum potential afforestation or deforestation in Europe (see, too, the study by Gálos et al., 2012, using the REMO RCM). Horizontal grid spacing in RCA4 is approximately 50 km over the EURO-CORDEX domain covering Europe, and the model has 24 vertical levels in the atmosphere. For their study, Strandberg and Kjellström applied lateral boundary forcing (pressure, humidity, temperature, and wind) every 6 h from ERA-Interim reanalyses. Sea surface temperature and sea ice extent were prescribed according to observations.

Three simulations were performed, differing only in the land cover map used, for the 30-yr period 1981-2010. The control simulation used RCA4's standard, present-day land cover map defined in the ECOCLIMAP (Champeaux et al. 2005) product. This map reflects the considerable agricultural activity in Europe, with large areas with low forest cover in central, western and southern Europe. To effect maximum afforestation, Strandberg and Kjellström used the LPJ-GUESS dynamic vegetation model (Smith et al. 2001 – see below) to produce a map of potential natural forest cover for Europe in equilibrium with present-day climate. Finally, maximum deforestation was implemented by converting forest fractions according to the potential forest cover to grassland in the control simulation.

In their analysis, Strandberg and Kjellström focused on winter (DJF) and summer (JJA) season mean

temperatures and precipitation, as well as daily minimum and maximum temperatures. Afforestation decreased albedo in both seasons, especially in regions in Eastern Europe with long snow cover and little forest cover. In contrast, deforestation increased albedo throughout the region, especially in the northern Baltic Sea region in winter.

Afforestation in Europe generally resulted in increased ET, as trees have a larger leaf area and deeper roots. This leads to colder near-surface temperatures in JJA. Deforestation gave the opposite effects, with warmer near-surface temperatures due to decreased ET in summer. In the Baltic Sea region, deforestation-induced reductions in ET coincide with the largest differences in fraction of forest (e.g., a reduction of 20%–35% in Scandinavia). Interestingly, ET increases by 20% over the Baltic Sea in JJA. Strandberg and Kjellström attribute this to a land-ocean coupling whereby warmer and drier air from the surroundings (due to reduced ET over land) favours increased ET over the Baltic Sea when it comes into contact with the sea.

Afforestation in winter resulted in a decrease in temperature in central and southern Europe that cannot be explained by albedo changes, since this is reduced in these months. Since ET is also low during winter, the changes were attributed to atmospheric circulation changes resulting from increased roughness.

The winter low pressure systems simulated by RCA4 lose their energy earlier because of increased friction over afforested areas due to their greater roughness, and in general afforestation leads to a simulated winter climate with less cyclonic activity in central Europe. Associated with this, the mean geopotential height at 500 hPa increased by 100 m in the Baltic Sea region.

Strandberg and Kjellström (2019) also found that the biophysical effects of afforestation or deforestation in Europe on daily minimum and maximum temperatures were stronger than the impacts on mean near-surface temperatures. In the case of afforestation, though DJF mean temperatures were reduced in most of Europe, there was a particularly strong warming of daily minimum temperatures (up to 2-6 ºC in Germany) that could be attributed to increased cloud cover and reductions in outgoing longwave radiation. During summer, on the other hand, the marked changes in mean temperatures were mainly caused by respective changes in daily maximum temperatures, i.e. decreases in the case of afforestation and increases for deforestation.Finally, by rerunning the simulations and confining the applied deforestation and afforestation changes to the western and/or eastern parts of the model domain, the authors also showed that the climatic effects of afforestation or deforestation in Europe were mainly local.

Belušić et al. (2019) followed up on the study of Strandberg and Kjellström (2019) and used a cyclone-tracking algorithm to study how the same idealized deforestation and afforestation scenarios affected the number and intensity of cyclones, and their effects on extremes of precipitation. Consistent with the results of Strandberg and Kjellström (2019), Belušić et al. (2019) found that the larger surface roughness after afforestation reduced the number of cyclones over Europe compared to the deforestation and control simulations, with differences of 20-80% near the Baltic Sea region 10% in regions near the west European coast and increasing towards the east to reach 80%. This resulted in a reduction in winter precipitation extremes of up to 25% across the domain.

Fig. 2: Outline of the biogeochemical (upper part in brown) and the biophysical influence (lower part in blue) of re-/afforestation or enhanced forest productivity in the Baltic Sea region on near-surface temperatures. The overall effect on near-surface temperatures varies by season and region, depending, for instance, on snow cover and incoming solar radiation (adapted from May et al., 2020).

Figure 2 summarizes the various biophysical and biogeochemical influences of re- and afforestation or enhanced forest productivity on near-surface temperatures in the Baltic Sea region. According to this, the decrease in surface albedo (resulting in increased absorption of incoming solar radiation at the land surface) is the only effect that leads to a warming of near-surface temperatures, while all the other effects lead to a cooling. As for the biogeochemical effects, these are increased carbon storage, weakening the radiative forcing, and more aerosols, which reduce the solar radiation reaching the land surface by additional scattering at the particles and more clouds. And as for the biophysical effects, these are increased roughness length, enhancing the turbulent fluxes of energy and momentum, and increased evapotranspiration in late spring and summer, which strengthens the fluxes of latent heat and weakens the fluxes of sensible heat. The magnitude of the overall cooling in the Baltic Sea region associated with re- and afforestation or enhanced forest productivity depends on the significance of the warming effect compared to the cooling from the other biophysical and biogeochemical effects.

Following up on their earlier, theoretical and observation-based studies in which changes in land management were shown to affect surface temperature to a degree similar to changes in land cover type (Luyssaert et al. 2014). Luyssaert et al. (2018) used the ORCHIDEE-CAN land surface model (further developed to explicitly take into account the biogeochemical and biophysical effects of land use change and management) coupled to the LMDZ atmospheric circulation model to investigate the trade-offs associated with using European forests to meet the climate objectives of the Paris Agreement. Their analyses demonstrate clearly that the biophysical effects of forest management must be taken into account in any assessment of climate mitigation strategies, with consequences for policy and forestry in the Baltic Sea region and beyond, e.g. in relation to the optimal balance of coniferous and deciduous forest in the region. Similarly, Kumkar et al (2020) used offline simulations with the CLM4.5 land surface model to quantify the sensitivity of turbulent fluxes and land

340 surfacetemperatures in Fennoscandia to scenarios of changes to forest composition and structure relative to their present-day values. They found that replacing conifers with deciduous forests could cool the surface by 0.16 K annually, and by 0.3 K is summer months, mainly as a result of their higher albedo, and identified important differences between developed and underdeveloped forests, the latter having lower evaporation rates as a result of their lower LAI and canopy height.

345 **Dynamic Global Vegetation Models applied to the Baltic Sea region**

Dynamic global vegetation models (DGVMs) are numerical models of terrestrial ecosystems that simulate the properties, dynamics and functioning of potential, natural and managed vegetation and their associated biogeochemical and hydrological cycles as a response to climate and environmental change. Prentice et al. (2007) summarize their historical development, design and construction 350 principles, as well as the processes typically included, their evaluation and examples of their application. DGVMs incorporate research and knowledge from different disciplines; including plant geography, plant physiography, biogeochemistry, including soil biogeochemistry, vegetation dynamics and demography, biophysics, agriculture and forest management. DGVMs have been used to study the observed and expected impacts on terrestrial ecosystems in the Baltic Sea region resulting 355 from climate and environmental change. An understanding of these impacts is a necessary first step to understanding the dynamics in coupled RESMs, where ecosystem change is allowed to influence local and regional climate through the biophysical feedback mechanisms outlined above.

Recent works has shown that in order to realistically simulate ecosystem carbon balance, climate responses, and ecosystem recovery following disturbances due to land-use change, management 360 interventions and natural disturbance processes such as fires and storms (Fisher et al. 2018; Pugh et al. 2019) it is important to incorporate the size- and age-structure and demography of vegetation and ecosystems explicitly, and to account for competitive interactions of growing vegetation stands comprising individuals or cohorts of different plant functional types. A number of DGVMs and land surface models (LSM) are now moving in this direction, away from a traditional tiled or area-based 365 (Smith et al. 2001) land surface representation, including the CLM4.5(ED) LSM (Moorcroft et al. 2001; Fisher et al. 2015; 2018) and the Functionally Assembled Terrestrial Ecosystem Simulator (FATES) vegetation demography submodel (Koven et al. 2020)), the POP (Population Orders Physiology) module for woody demography in the CABLE LSM (Haverd et al. 2013, 2014, 2018), the RED module in the JULES LSM (Argles et al. 2020) and the SEIB-DGVM (Sato et al. 2007). To 370 date, however, no demographic model has been applied to study the Baltic Sea region specifically (though see Kumkar et al (2020) for an application using CLM4.5) apart from the LPJ-GUESS (Smith et al. 2001, 2014) DGVM. LPJ-GUESS explicitly represents the size, age structure, spatial heterogeneity and temporal dynamics of co-occurring cohorts of plant functional types (PFTs) i.e. classifications of plants according to their physical, phylogenetic and phenological characteristics 375 (Prentice et al. 2007; e.g. boreal or temperate, evergreen or deciduous, and broadleaved or needle leaved trees in the Baltic Sea region, and herbaceous species) or species (Hickler et al. 2012) that compete in natural and managed stands (forestry, crops and pasture), in response to climate, atmospheric CO_2, and nitrogen (N) availability. As the stand structure evolves in response to environmental change and impacts the availability of key resources, then growth, survival and the 380 outcome of competition are affected.

LPJ-GUESS represents different land use and management in separate stands (Lindeskog et al. 2013). The fraction of the grid cell covered by each stand (forest, natural, cropland etc.) type can change in time, following external land use datasets (e.g. Hurtt et al. 2020). LPJ-GUESS also allows for detailed management interventions for representative crops (represented as crop functional types, CFTs), 385 grassland grazing, mowing and fertilisation (Olin et al. 2015a, b) and clearcut and continuous-cover forest management (Lagergren & Jönsson 2017). Disturbances due to management actions such as forest clearing, prognostic wildfires and a stochastic generic disturbance regime induce biomass loss and reset vegetation succession (Smith et al. 2001). N cycle-induced limitations on natural vegetation and crop growth, C-N dynamics in soil biogeochemistry and N trace gas emissions are included (e.g.

390   Smith et al. 2014[1]; Olin et al. 2015a, b) as well as BVOC (isoprene and monoterpene) emissions (Hantson et al. 2017).

LPJ-GUESS output variables describe the vegetation state (PFT/species composition, LAI, vegetation height, biomass, tree density, burnt area), variables relating to the state and functioning of the soil (water content, C and N content, temperature, runoff, N leaching, loss of dissolved organic C and N),
395   and climatically important fluxes to and from each simulated stand (evapotranspiration, gross and net primary productivity, autotrophic and heterotrophic respiration, fluxes from wildfires, CH_4 and N trace gases, BVOCs, and net ecosystem carbon exchange.

Modeling terrestrial ecosystems in the Baltic Sea region

LPJ-GUESS has been applied in many studies to simulate terrestrial ecosystems in the Baltic Sea
400   region, under current, future as well as historic and pre-industrial climate conditions. Koca et al. (2006) simulated the impacts of climate change on natural ecosystems in Sweden in response to different regional climate change scenarios. In all the climate scenarios considered, the authors observed an increase in plant productivity and leaf area LAI, and a northward and upward advance of the boreal forest treeline by the end of the 21st century. The current dominance of Norway spruce and
405   to a lesser extent Scots pine was found to be reduced in favor of deciduous broadleaf tree species in future scenarios across the boreal and boreo-nemoral zones. These changes are consistent with earlier studies (Miller et al. 2008) of the effects of climate and biotic drivers on Holocene vegetation in Sweden and Finland where observed changes to the northern distribution limits of temperate trees and species at the tree line were attributed to millennial variations in summer and winter temperatures.

410   Hickler et al. (2012) re-parameterised the most common European tree species in LPJ-GUESS and forced the model with AOGCM climate scenario output, downscaled to a spatial resolution of 10 × 10′. Climate change and CO_2 increase resulted in large-scale successional shifts, with 31–42% of the total area of Europe projected to be covered by a different vegetation type by the year 2085 depending on the scenario used. Consistent with the earlier results of Koca et al. (2006), trees replace tundra in
415   arctic and alpine ecosystems, and temperate broad-leaved forest replaces boreal conifer forest in the Baltic Sea region.

Regional Earth System Modeling with interactive vegetation dynamics in the Baltic Sea region

Coupled regional Earth System Models (RESMs) extend RCMs to include the terrestrial biosphere as an integral dynamic component interacting in a two-way coupling with the atmosphere, with
420   representations of both vegetation dynamics and terrestrial biogeochemistry. Such a framework allows for modelled natural and managed ecosystems to respond to climate and environmental change, and influence local and regional climate through the biophysical feedback mechanisms outlined above.

RCA-GUESS was the first published and evaluated RESM (Smith et al. 2011) to include the
425   terrestrial biosphere as an integral dynamic component, and couples LPJ-GUESS to the RCA3 RCM (Samuelsson et al. 2011). In its RCA-GUESS configuration, LPJ-GUESS is driven by the daily mean temperature, soil water content, precipitation and downward shortwave radiation simulated by RCA3, and CO_2 concentration is read from the same source used to force RCA.

In its uncoupled configuration, the land surface scheme of RCA3 uses ECOCLIMAP to specify the
430   cover fractions of two vegetated land surface tiles, one representing the type of forest (broadleaved or needleaved) and the other open land (including crops, pasture and grassland) for each grid cell in its domain.

In RCA-GUESS, LPJ-GUESS replaces the static ECOCLIMAP land cover description and aggregates its vegetation fields to update the tile fractions, their type and associated LAI. The specific forest PFT
435   types simulated by LPJ-GUESS are aggregated into needleleaved and broadleaved trees before

10   1

providing the information to RCA, while open land includes a varying coverage of herbaceous vegetation.

By changing the relative fractions and types in RCA, the LPJ-GUESS fields determine and update dynamically the surface albedo, LAI, surface roughness and conductance in RCA grid cells. For example, albedo is calculated in RCA using a weighted average of prescribed albedo values for needle leaved and broadleaved trees, open land vegetation, snow and bare soil. Similarly, the fluxes of sensible and latent heat are calculated as weighted averages of the individual tiles.

Terrestrial CO_2 exchange is simulated by LPJ-GUESS, enabling biogeochemical ecosystem responses to be assessed consistently with the biophysical land-atmosphere interactions (Zhang et al. 2014). However, the atmospheric CO_2 concentrations are not updated over the limited domain covered by RCA. Thus, though biophysical feedback loops are closed in RCA-GUESS, biogeochemical feedback loops are open.

Wramneby et al. (2010) used RCA-GUESS to identify hot spots of biophysical vegetation-climate feedbacks for future climate conditions in Europe. Two simulations – feedback and non-feedback – were run over Europe for 1961-2100 to isolate the effect of feedbacks from vegetation dynamics. In the feedback simulation, RCA and LPJ-GUESS were coupled throughout the entire simulation period. In the non-feedback simulation, land cover in RCA was prescribed and fixed in the full simulation period from the long-term means from LPJ-GUESS output in the coupled simulation for 1961-1990. The difference between the climate change signal (2071-2100 minus 1961-1990) from the feedback simulation and the corresponding signal from the non-feedback simulation was used to calculate the additional contribution of the vegetation-climate feedback to the background climate changes simulated by RCA3, driven by lateral GCM forcing.

Wramneby et al. (2010) showed that the snow-masking effect of forest expansion and greater LAI in the Scandinavian mountains, and consequent reductions in albedo, enhanced the winter warming trend. In central Europe, the stimulation of photosynthesis and plant growth caused by the increased CO_2 concentration, longer growing seasons and warming mitigated the future warming through a negative feedback due to enhanced ET associated with the increased vegetation cover and LAI.

Zhang et al. (2014; 2018) applied RCA-GUESS over the Arctic domain of the Coordinated Regional Climate Downscaling Experiment (CORDEX-Arctic) - which includes the northern part of Baltic Sea region - to investigate the role of the biophysical feedbacks from vegetation in the Arctic region under three different climate scenarios (RCP2.6, RCP4.5 and RCP8.5). Zhang et al. found that warming and CO_2 increases promote productivity increases, LAI increases and treeline advance into the Arctic tundra, with the consequence that two biophysical effects have the potential to alter the spatiotemporal signal of future climate change in the Arctic region: interactive vegetation results in albedo-mediated warming in early spring and ET-mediated cooling in summer, amplifying or modulating local warming and enhancing summer precipitation over land.

2.2 Ocean-atmosphere coupling

The treatment of ocean - atmosphere exchange of momentum, heat, and mass substantially differs between coupled and uncoupled models. Basically, in the coupled mode the ocean is driven by fluxes and sea level pressure calculated in the atmosphere model (e.g. Fig. 3) and used to drive the coupled ocean model which in turn communicates simulated fields of sea ice and surface water temperature (SST) to the atmosphere model. By contrast, uncoupled ocean models use atmospheric forcing fields (Passively Coupled Ocean, PCO) to calculate air sea fluxes using a bulk formula. Standalone atmosphere models usually read prescribed fields of sea ice and SST from reanalysis data sets or model data to calculate fluxes.

Figure 3: Mass, momentum and heat exchange as realized in the atmosphere - ocean model RCA4-NEMO. ICA=interactively coupled Atmosphere; PCA=Passively coupled Atmosphere; ICO=Interactively coupled ocean; PCO =passively coupled ocean. Source: Gröger et al. (2015).

2.2.1 Impact on mean climate

One of the main questions addressed so far is if an interactively coupled atmosphere-ocean model would significantly change the long term climate compared to their stand alone atmosphere and ocean modules. This is investigated in a number of studies (e.g. van Pham et al., 2014; Tian et al., 2013 Gröger et al., 2015; Primo et al., 2019; Kelemen et al., 2019; Akhtar et al., 2019; Cabos et al., 2020; Gröger et al., 2021). Van Pham et al. (2014), developed a Regional Atmosphere Ocean General Circulation Model (RAOGCM) built upon the ocean model NEMO coupled to the atmosphere model COSMO-CLM (the COSMO model in Climate Mode, hereafter denoted as CCLM) for the EURO-CORDEX domain. The coupling domain encompassed the Baltic Sea and the North Sea until 4°W and 59°N. As forcing as well as at the lateral model boundaries the authors applied ERA-interim reanalysis data. Noteworthy, the coupled system showed systematically lower T2m air temperatures in the Baltic Sea and North Sea in the long term mean compared to the uncoupled atmosphere model. Consequently, interactive coupling reduced the models mean bias in T2m compared to the E-OBS observational data set as a reference. Interestingly, the authors found most significant changes between coupled and uncoupled runs over continental areas of central and eastern Europe, i.e. far remote from the coupled areas. Analysis of the modeled wind field indicated these areas were situated downwind from the coupled domain North Sea and Baltic Sea implying a more complex pattern of atmospheric advection of temperature anomalies which were not further investigated.

However, similar experiments of Gröger et al. (2015) using nearly the same ocean model NEMO but coupled to the regional atmosphere model RCA4 were somewhat contradictory. In their setup forced by ERA40 reanalysis data with lateral bondaries prescribed by ORAS4 (Balsameda et al., 2013) the coupled system showed generally warmer near surface air temperatures over the Baltic Sea compared to the uncoupled RCA4 model. Furthermore, no significant differences were found in air temperatures over land between coupled and uncoupled simulations. With respect to sea surface temperatures Gröger et al. (2015) found the strongest differences in the Baltic Sea where SSTs in both the coupled, and uncoupled system were too cold in winter compared to satellite products. However, winter SSTs were significantly higher in the coupled model (thereby reducing the bias) due to seasonally varying feedback loops controlling the ocean-atmosphere heat exchange. Figure 4 sketches the main mechanisms building up atmosphere-ocean feedbacks during summer and winter that control the SST in the Baltic Sea.

Figure 4:a) positive winter feedback loop. b) negative summer short circuit. Drawn after Gröger et al. (2015).

520 Winter thermal - wind mixing positive feedback

During winter the Baltic Sea is usually warmer than the atmosphere supporting a net heat flux out of the ocean.

During ocean offline simulations, in which the ocean model was forced with ERA40 atmospheric reanalysis data, simulated winter SSTs in the Baltic Sea showed a strong bias compared to observed 525 SSTs. That was mainly caused by a cold bias of the ERA40 data set over Europe. In the coupled mode, driven by the same data set at the lateral boundaries the bias nearly vanished due to a thermal feedback loop between the ocean and the atmosphere which resulted in stronger vertical mixing and increased transport of warmer deep waters to the surface (thereby reducing the cold bias at the surface compared to the uncoupled simulation). This is shown in Figure 4a. In the coupled model the 530 atmospheric boundary layer is disturbed by warm anomalies generated in the Baltic Sea. This promotes stronger winds that in turn feed back to the ocean with stronger vertical mixing thereby increasing heat exchange with warmer deeper water layers. As a result the ocean model's cold bias reduces in the Baltic Sea compared to the ocean standalone model which uses prescribed atmospheric boundary conditions that can not respond to SST anomalies (Gröger et al., 2015).

535 Summer thermal short circuit

During summer the above feedback loop is bypassed by the inverse thermal air sea contrast. Since the atmosphere is generally warmer than the ocean in summer, any wind induced upward mixing of cold deep water will tend to stabilize the atmospheric boundary layer with negative effect on wind strength (Figure 4b). This was demonstrated at stations in stratified areas of the Baltic Sea and in the North Sea 540 using lead correlation analysis between 10 m wind velocity and SST after a short term event of strengthened winds (Gröger et. al., 2015). During the first 70 hours after the event wind and SST were negatively correlated (with a peak r=0.7 at around 30 hours) implying decreasing SST with stronger wind mixing with colder deep waters. After 70 hours, correlation turned to positive values with a peak (r=0.7) around 130 hours as the colder water surface stabilizes the atmospheric boundary layer and 545 thus promotes lower wind speeds. In the following wind mixing ceases again giving rise to heat gain from the warmer atmosphere again Gröger et al. (2015).

These results highlight the importance of thermal air sea coupling in mid-latitude marginal seas and are supported by a number of different studies. Tian et al. (2013) drove a coupled ocean atmosphere model by ERA-Interim reanalysis data (ERA-I). Similar to Gröger et al. (2015) the authors found too 550 cold SSTs in winter but with a substantial lower bias in the coupled model. No detailed feedback analysis was carried out but it is likely that the positive winter feedback was also present in the model by Tian et al. (2013). Moreover, Keleman et al. (2019) applied a model which couples an atmosphere model for the Euro-Cordex region to regional ocean models for the Mediterranean, the North Sea and the Baltic Sea. They found a significant improvement of winter precipitation patterns over eastern 555 Europe through the altered representation of SSTs. However, SSTs themself were not validated so that a general conclusion about the performance of the whole system can not be drawn. Primo et al.

(2019) used the same model showing that the air sea coupling can improve the representation of heat and cold waves but concluded that a general judgement of the whole system is difficult to draw but depends on the variable considered.

560 Impact on climate indices

Apart from the thermal coupling effect on mean climate we now consider temperature related climate indices often used in regional climate assessments such as CORDEX (e.g. Jacob et al., 2014; Teichmann et al., 2018; Kjellström et al., 2018; Gröger et al., 2021). The indices are strongly related to the ocean heat content and thus are sensitive to the coupling. In particular, we here focus on three
565 indices with importance for human health, agriculture, and ecosystem of the Baltic Sea: (1) number of tropical nights defined as nights where the daily minimum temperature does not fall below 20°C (e.g. Fischer and Schär, 2010; Teichmann et al., 2018; Meier et al., 2019; Gröger et al., 2021), (2) number of frost days defined as days where the daily minimum temperature falls below 0°C, and (3) number of warm periods defined as at least 3 consecutive days where the daily maximum temperature reaches
570 20°C. For our analysis we take available data from hindcast runs as described in Gröger et al., (2015). All indices are derived from the reference period 1970-1999 from both the coupled and the uncoupled simulation. Both runs are driven with ERA40 atmospheric reanalysis data at the lateral model domain boundaries. Lateral boundary conditions were set according to the ocean reanalysis ORAS4 (Balsameda et al., 2013). For details about coupling we refer to Gröger et al. (2015) and Dieterich et
575 al. (2019).

Figure 5a displays the simulated number of tropical nights simulated with the coupled ocean atmosphere model RCA4-NEMO (Wang et al. 2015; Dieterich et al., 2019; Gröger et al., 2019; Gröger et al., 2021). A clear land sea pattern is seen with only sporadic occurrences over land with the exception of the southern part of the Iberian Peninsula and the Pannonian basin south of the
580 Carpathians. The higher effective heat capacity of the ocean is responsible for the frequent occurrences over the Mediterranean, and the southern North Atlantic sector which also includes the Bay of Biscay. The thermal effect of the Baltic Sea water body is obvious. Unlike the North Sea, which receives colder waters from the North Atlantic, the Baltic Sea has very limited exchange of waters with the adjacent North Sea. In addition, a strong seasonal thermocline during summer limits
585 also the exchange with colder waters from deeper layers. These two processes support a strong warming of the Baltic Sea during summer. Consequently, that prevents the air temperature from falling below 20 °C during warm periods in the second half of the summer. As a result, the Baltic Sea displays a range of tropical nights that matches the range found further to the south like north of the Black Sea or in parts of the Atlantic west off northern Iberia (Figure 5a, left). Figure 5a (right)
590 demonstrates that the above described thermal effect over the Baltic Sea is much stronger pronounced in the coupled model including the dynamic ocean model. As a result, over the southern Baltic Sea the number of detected tropical nights within the reference period increases between 50% and 100% compared to the atmosphere standalone model.

Figure 5b, left shows the number of frost days during the reference period. A clear land sea pattern is
595 seen with strongly diminished occurrences over the open ocean areas in the North while they are completely absent over the southern Mediterranean and southern part of the Atlantic. Again, the different thermal behavior between the North Sea and the Baltic Sea is obvious. The Baltic Sea behaves thermally like the continents supporting a large number of frost days. This is related to the strong winter halocline that hampers wind forced mixing and convective mixing with deep waters.
600 Consequently, the upper layer water body of the Baltic Sea can rapidly cool ~~under~~during winter. By contrast the adjacent North Sea effectively damps the occurrences of frost days. However, a pronounced east west gradient is visible with lower occurrences in the west. Here, warmer waters from the Atlantic enter the North Sea and spread southward. The eastern part of the North Sea is influenced by low salinity waters derived from the Baltic Sea. These waters flow northward along the
605 Norwegian coast and impose a haline stratification there. This results in a similar thermal behavior as discussed for the Baltic Sea. The southern part of the eastern North Sea, namely the German bight is only shallow and supports rapid cooling. Altogether, this builds up the east west gradient seen in

Figure 5b (left). Generally, these thermally forced processes are represented in both the coupled and uncoupled model version but in the coupled model the number of frost days is significantly reduced nearly everywhere over the Baltic Sea (Figure 5b, right). Here the aforementioned winter mixing feedback loop operates, i.e. stronger mixing in the coupled model increases the winter sea surface temperature with positive feedback on wind speed and resulting in a significantly higher sea surface temperature and reducing the number of frost days. Over the North Sea, coupling generates a positive anomaly along a band between the 2-4°E meridian. It is likely that this reflects shifts in the gradients caused by slightly altered flow paths of the water masses derived from the Baltic Sea and the North Sea.

Figure 5:a) left: Number of tropical nights diagnosed from the coupled regional ocean atmosphere model during the reference period 1970-1999. right: Difference [%] of the coupled minus the uncoupled model. b) same as a) but for the number of frost days. c) left: number of periods of at least 3 consecutive warm days (days where the daily maximum temperature exceeds 20°C). right: Difference [%] of the coupled minus the uncoupled model.

Finally, the coupling effect of warm periods is displayed in Figure 5c. In the Baltic Sea such periods are an important precondition for the occurrence of cyanobacteria blooms during summer. Also here, the southern Baltic Sea turns out to be a hot spot for the effect of interactive air sea thermal coupling as the number of such periods in the coupled model exceeds the corresponding number in the standalone atmosphere model by several orders of magnitude. Here the effect of the aforementioned summer thermal shortcut is seen. Enhanced mixing by winds brings cooler waters from depth to the surface. The cooler surface water likewise cool the air temperatures which imposes a stabilizing effect

630   on the atmospheric boundary layer over sea thereby damping wind strength again (see Gröger et al., 2015 for details). This facilitates the development of longer lasting warm periods under summer.

So far, we discussed thermal effects of damping (in case of frost days) and amplifying (warm days, tropical nights). The associated feedback loops are more realistically represented in the fully coupled model as previously explained. However, a significant effect apart from the active coupling area over
635   land seems to be rather weak. On the other hand we note that the interactive coupling area must be considered small compared to the whole domain. Thus extending the area of interactive coupling by e.g. including also the Mediterranean or larger parts of the North Atlantic may result in more intense effects of using coupled models (Primo et al., 2019; Keleman et al., 2019; Akhtar et al., 2019; Cabos et al., 2020).
640

2.2.2 Impact on extreme events

Apart from the representation of mean climate, many air sea coupling processes are important in generating hazardous events such as extreme precipitation, storm track paths or flooding (see also Rutgersson et al., 2021). Often these events are generated remotely over the open ocean and thus
645   require a realistic representation of the ocean's surface. Therefore, when no high resolution ocean model is coupled to the regional atmosphere model the sea surface has to be represented by available products for sea surface temperatures (SSTs) and sea ice. These products are often limited in quality and frequency. For example, ERA40 SSTs often used in uncoupled atmosphere simulations are based on weekly or even monthly frequency (Fiorino, 2004; Uppala et al., 2005). Consequently, many
650   studies compared coupled and uncoupled models with respect to the representation of extreme events in hindcast simulation. More recent products like e.g. ERA5 may improve the situation by providing a higher spatial and temporal resolution.

Jeworrek et al. (2017) diagnosed a better representation of atmospheric conditions favorable for the
655   occurrence of convective snowbands. The authors attributed this improvement to a more accurate simulation of SSTs and subsequent air sea heat and moisture fluxes in case the atmosphere model RCA4 was coupled to the ocean model NEMO setup for the North Sea and Baltic Sea. The importance of accurate SSTs for the representation of snowbands has been recognized early by Gustafsson et al. (1998).
660
Comparing two regional ocean atmosphere models in coupled and uncoupled mode Ho-Hagemann (2015, 2017) found that interactive air sea coupling can alter extreme precipitation over land. Ho-Hagemann et al. (2015, 2017) pointed out that the coupled model COSTRICE improved the low level large-scale moisture convergence over the North Atlantic and the moisture transport towards Central
665   Europe. As a result, the simulated summer heavy rainfall improved compared to the stand-alone atmospheric model CCLM. This was demonstrated for several flood events in Central Europe. A diagram displaying cause and effects as well as feedbacks between earth system components is shown in Figure 6 to explain the physical mechanism behind the better representation of heavy rainfall. The main effect is an altered SST in the coupled model further influencing wind speed and evaporation (so
670   called Wind-Evaporation-SST (WES) feedback, Xie & Philander (1994)). When wind speed increases over an area, evaporation increases and so the latent heat flux is enhanced often leading to ocean cooling over this area. The lowered SST generates a horizontal SST gradient on the sea surface and also increases the land-sea heat contrast which in turn supports increasing wind speed. Stronger wind over the North Sea then generates a larger latent heat flux from the ocean to the atmosphere, and
675   intensifies the low over Central Europe and the North Sea, which both support the large-scale moisture convergence from the North Sea to Central Europe. A review article about the influence of atmospheric ocean interactions on heavy rainfall over Europe is available by Ho-Hagemann and

Rockel (2018).

Figure 6: Air-sea feedback and interaction diagram. For each arrow, the initial status indicates that the source quantity is increasing, and the sign (− or +) indicates the changing tendency of the target quantity. Colours denote the group of changes or states over sea (blue), land (brown) and the land-sea interactions (green). [Source: Ho-Hagemann et al. (2017)]

A better representation of extreme and mean temperatures in the CCLM atmosphere models is also reported in Primo et al. (2019) and Kelemen et al. (2019) when coupled to regional high resolution ocean models for the North Sea, the Baltic Sea, and the Mediterranean. Akhtar et al. (2014) analyzed 11 historical medicane events simulated by the atmosphere-only model CCLM and coupled model CCLM-NEMOMED12 with different horizontal atmospheric grid spacings of 0.44, 0.22, and 0.08 degrees. There, the coupled simulations improved significantly compared to atmosphere-only simulations at higher atmospheric grid resolution (0.08). The characteristic features of medicanes, such as warm cores and high wind speeds, are more intense in coupled simulations compared to atmosphere-only simulations. Akhtar et al. (2019) demonstrated likewise improved simulations of cyclones over the Mediterranean in the coupled system model of CCLM and two ocean models NEMO-Nordic and NEMOMED12 compared to the atmosphere-only with prescribed SSTs.

The Impact of air-sea coupling on simulations of mid-latitude cyclones was recently investigated using an ensemble approach by Ho-Hagemann et al. (2020). The coupled model GCOAST-AHOI reduces the large spread of wind speed, mean sea level pressure, surface temperature, cloud cover as well as radiation fluxes amongst ensemble members of the atmospheric model during the storm Christian occurring from 27 to 29 October 2013 in northern Europe.

2.2.3 Influence of the size of the coupling area

As outlined above the size of the air - sea coupling area will influence how strong the coupling effect will be and how far it may propagate further over land. Table 2.2.3.1 lists several RAOGCMs applied for the Baltic region, which have been developed for various areas within the recent decade. In these RCSMs, the atmospheric models cover different domains such as EURO-CORDEX domain, European domain, or the Arctic. The domain of the ocean model can be global with increased resolution over the North Sea and Baltic Sea as in MPIOM (Sein et al. 2015), or regional as in the other RCSM setups. For example, in a common NEMO setup used by several RAOGCMs (e.g., Van Pham et al. 2014; Gröger et al. 2015; Wang et al. 2015; Dieterich et al. 2019; Akhtar et al. 2019; Primo et al. 2019), the Baltic Sea and North Sea regions are considered. In other coupled systems e.g.,

Ho-Hagemann et al. (2015, 2017, 2020), the ocean model domain extends from the Baltic Sea and North Sea region into a part of the North Atlantic. Moreover, one atmospheric model can be coupled to more than one ocean model as in Akhtar et al. (2019) and Primo et al. (2019).

Models	Atmosphere and others (Domain)	Ocean and Sea ice (Domain)	References
CCLM-NEMO-Nordic	CCLM (EURO-CORDEX)	NEMO/LIM3 (Baltic Sea & North Sea)	Van Pham et al. (2014)
CCLM-NEMO-Nordic-NEMOMED12	CCLM (European)	1. NEMO/LIM3 (Baltic Sea & North Sea) 2. NEMOMED12 (Mediterranean Sea)	Akhtar et al. (2019); Primo et al. (2019); Kelemen et al. (2019)
COSTRICE	CCLM (EURO-CORDEX)	TRIMNP/CICE (Baltic Sea, North Sea & a part of North Atlantic)	Ho-Hagemann et al. (2015, 2017)
GCOAST-AHOI	CCLM/HD (EURO-CORDEX)	NEMO/LIM3 (Baltic Sea, North Sea & a part of North Atlantic)	Ho-Hagemann et al. (2020)
RCA4-NEMO	RCA4 (EURO-CORDEX)	NEMO/LIM3 (Baltic Sea & North Sea)	Wang et al. (2015); Gröger et al. (2015); Dieterich et al. (2019)
ROM	REMO/HD/HAMOCC (Arctic, EURO-CORDEX)	MPIOM (Global)	Sein et al. (2014, 2015)
RCAO	RCA (Baltic Sea region)	RCO (Baltic Sea)	Döscher et al. 2002; Räisänen et al., 2004; Döscher and Meier, 2004; Meier et al. 2004)
HIRHAM-HBM	HIRHAM5	HBM (Baltic Sea)	Tian et al., (2013)

Table 2.2.3.1: Regional coupled climate models and their air-sea coupling domains.

A recent assessment of regional coupled modeling (Schrum, 2017) emphasized that both the location and extension of the coupled region (Sein et al., 2014), the coupling frequency (Fang et al., 2009), as well as the quality of initialization and boundary forcing (Wei et al., 2014) is critical. In the following, we focus on the size of the coupling area and consider its potential impact on climate simulations. We will elaborate options about suitable sizes for the coupling area as well.

Sein et al. (2014) pointed out that the choice of the coupled model domain based on simple geographical arguments is not sufficient, and decisions should be made based on the fundamental understanding of oceanographic and atmospheric processes and their feedbacks. Mikolajewicz et al. (2005) discussed the challenges for the global mass and energy balance arising from coupling between a global model and a regional model. Inconsistencies can occur when the inflow to the

coupled region is calculated based on the global forcing while outflow is calculated based on the regionally coupled model solution. Using a larger domain for the ocean model, on the one hand, gives the ocean more degrees of freedom (Mikolajewicz et al., 2005) by putting the boundary conditions in the deep ocean in the North Atlantic and not in the North Sea. On the other hand, more effects of air-sea coupling over the North Atlantic on the simulated climate over Europe can be taken into account.

In studies where the coupling domain is comparatively large to the total domain often comprising multiple seas with a large heat inventory, the air sea coupling effect is often found to extend far inland (e.g., Somot et al. 2008, Ratnam et al. 2009, Ho-Hagemann et al. 2015, 2017). Gröger et al. (2021) hypothesize that SST anomalies must have a critical extension and be linked to a sufficiently large heat content of the underlying ocean to impose a significant effect on large-scale atmospheric circulation. Otherwise, the fast transport (relative to the ocean) within moving air masses supports a rapid dispersion of temperature anomalies in the atmosphere. Li (2006) indicated that varying the SST over the Mediterranean Sea could initiate atmospheric teleconnections, which can influence precipitation over remote regions such as the Europe-Atlantic region.

A known problem for many atmospheric models (Vidale et al. 2003) is a dry bias over large areas of mid-latitude continents. Sensitivity experiments with different regional models and different resolutions showed that interactive coupling can reduce this bias in those models that include parts of the North Atlantic in the coupled domain (Ho-Hagemann et al., 2017). A large part of precipitation over Europe is linked to moisture originating from the North Atlantic. Thus, a realistic moisture convergence over the North Atlantic-European region is essential to obtain good precipitation patterns. The authors concluded that in the presence of precipitation biases of the atmosphere models, the realistic simulation of air sea feedbacks enhances the large scale wind and evaporation via altering the sea surface temperature and the land sea heat contrast, and therefore, reduces the dry bias.

2.2.4. Atmosphere - sea ice - ocean modeling

The Baltic Sea is seasonally covered by sea-ice and the importance of this ice's influence on the general state of the Baltic Sea is unquestionable. Ice cover creates a barrier between the atmosphere and the sea that results in a direct impact on the exchange of mass, energy and momentum. Ice significantly modifies or even eliminates the interaction between the atmosphere and the sea. Furthermore, ice and snow reflects even 90 % of incoming solar radiation instead of high absorption of sea surface. This albedo related positive feedback effect is the main reason behind the amplification of climate change in the polar regions.

In a coupled modeling system, the most important prognostic sea ice parameters are ice/snow surface temperature, albedo, ice concentration, growth rate of ice as well as surface and bottom roughness since those control radiation, heat, moisture and momentum fluxes at the atmosphere-ice-ocean interface. The growth rate and temperature of sea ice impact on salt flux between ice and ocean. However, due to low salinity of the northern Baltic which experiences annual ice cover, that mechanism doesn't have a significant effect.

Theoretical frameworks of presently used sea ice models in climate applications were established already in the 1970's. The thermodynamical evolution of ice and snow is based on the classical heat conduction law, resolved numerically firstly by Maykut and Untersteiner (1971). The model resolves vertical temperature and salinity structure and surface temperature iteratively. The present community sea-ice models LIM-3/SI[3] (Rousset et al., 2015; Vancoppenolle et al., 2009) and CICE (Hunke and Dukowitc, 1997) apply this classical framework but include detailed parametrizations of snow, flooding, snow-ice formations, melt ponds, albedo and brines. For climate applications, the vertical structure is usually resolved for 1 to 3 layers. The one layer model assumes a linear temperature profile on ice. This is a valid approximation for Baltic Sea where thermodynamically grown sea ice

rarely exceeds one meter.

The Mmomentum balance equation of sea ice includes wind stress, bottom stress due to the ocean current, sea surface tilt, internal stress of the ice pack and the Coriolis force. The main uncertain term is the internal stress of sea ice. In the Baltic, this term can be dominant due to the large effect of the coastline and island. In present coupled models, two rheological solutions are commonly used. The Hibler (1979) viscous-plastic rheology (VP) implies that under very low strain rates the bulk and shear viscosities are constant and the model produces linear viscous behavior; otherwise the viscosities are calculated according to the plastic flow rule. VP rheology resolves non-linear behavior of Baltic sea ice dynamics well (Leppäranta et al. 1997). LIM-3/SI[3] model apply VP-rheology and it's a rheological choice of the NEMO-Nordic model (Pemberton et al. 2017; Hordoir et al., 2019). However, since VP-rheology is computationally demanding, numerically more feasible elasto-viscous-plastic rheology (EVP; Hunke and Dukovich, 1997) is used in the CICE model. It also widely used in Baltic Sea applications (Meier, 2002; Jakacki and Meler, 2018; Janecki et al, 2018).

The Tthird element of the sea ice models is a resolving of ice thickness distribution g(h) (Thorndike et al, 1975). In the classical Hibler (1979) model, g(h) is approximated with two ice thickness categories: thin ice, interpreted as open water, and thick ice. Choice of the minimum ice thickness has an impact on the modeled ice edge. Ridging of ice is taken into account since ice thickness can freely increase during the convergent ice motion, although ice concentration is constrained to be 1.0 at maximum. To solve g(h) numerically, several ice categories are needed (Hibler, 1980; Flato and Hibler, 1995). An alternative approach is to solve the ice concentration and mass for each ice category or ice type in a Lagrangian ice thickness space (Bitz et al, 2001). Multi-category sea-ice models apply redistribution functions to describe an average evolution of the pack ice deformation processes. Several deformation processes, such as compacting, rafting and ridging, are possible during a single time step (Haapala et al. 2005). This mimics real behavior of the pack ice in a continuum scale.

These three governing equations are strongly coupled. Firstly, sea ice mobility is non-linearly related to the ice thickness and concentration. Thin or low concentration pack ice drifting close to free drift speed but even 0.5 meters thick solid ice cover can be stationary under action of strong winds in the Bay of Bothnia. In turn, ice motion generates fractures and leads on ice pack which enhance mobility, but more importantly increase sea ice mean thickness by new ice growth in leads and formation of pressure ridges in compression. Due to ice dynamics, mean ice thickness in the coastal boundary zone is thicker than in landfast ice regions (Oikkonen et al. 2016; Ronkainen et al, 2018). Mobility of pack ice has large consequences on formation of coastal leads which are local sources of heat and moisture.

In the Baltic Sea, correct modeling of landfast ice, which can extend several kilometers from shore, is essential. In the CICE, landfast ice regime is parameterized by introducing basal stress due to grounded ridges (Lemieux et al, 2016). A simplified approach is to assume that the landfast ice regime is dependent on sea depth (Palosuo, 1966). This approach has been used in several applications and implemented on the Nemo-Nordic (Pemberton et al., 2017).

A study of Baltic Sea climate variability based on the Hibler model type coupled with Bryan-Semtner-Cox, z- coordinate baroclinic ocean model (the Rossby Centre Ocean model, RCO), developed by M. Meier (Meier 2002a, 2002b, Meier and Dorsher 2002), was performed in the early 2000's. RCO and the University of Helsinki sea-ice model (HIM), has been used for analysis of future ice conditions of the Baltic Sea region, (Haapala et al. 2001). Based on these models the authors made two 10-year simulations representing preindustrial and future scenarios of Baltic Sea ice conditions. Both models, on a global scale, delivered similar results, however on a regional scale there was a large variation between model results. Studies show dramatic decreases of ice extent, also the calculated ice thickness was lower in the scenario simulation and it is expected, based on this simulation, that Archipelago Sea and Quark will not be covered by ice in the future. The influence of greenhouse gas emissions (A2 and B2 IPCC scenarios that represent the climate of the late 21st century - 2071-2100) on ice conditions was performed based on four RCOA (RCOA is a coupled RCO with the atmosphere model) model simulations. Each analyzed scenario was made using the same model, but with different

boundaries created by two different climate models. Results showed that the mean annual ice volume will decrease by about 80% or more, a reduction of annual maximum ice thickness up to 60% and a decrease of ice days over 90%. All of the results are locally dependent. They also concluded that total ice area depends on air temperature with less influence from other physical factors.

Recently two present day coupled ice-ocean models have been developed for the Baltic Sea region – ice part (LIM3.6) was evaluated in the NEMO-NORDIC model (Pemberton et al., 2017), that covers Baltic and North Seas and B-CESM (Jakacki and Meler, 2018), only for the Baltic Sea area. The model is based on the Community Earth System Model where sea-ice is represented by CICE and the oceanic part is the Parallel Ocean Program. Both are working well as present day climate models.

2.2.5 Coupling strategies and pitfalls comparing coupled and uncoupled models

In recent years two different coupling architectures have been used and actively developed. On the one hand there is a single executable concept that uses the coupler as a driver to call different earth system components and handle the communication between them. Examples include the Earth System modeling Framework (ESMF; Hill et al., 2004), CPL7 (Craig et al., 2012) or C-Coupler1 (Liu et al., 2014). This approach might require a substantial degree of adaptation of existing code to fit into the coupling framework. With respect to the performance of coupled systems single executable design (CPL7) has been shown to be superior to multiple executable design (CPL6) for today's configuration of coupled GCMs (Craig et al., 2012). On the other side, there is the concept of the OASIS and YAC coupler (Valcke, 2015; Hanke et al., 2016)) that orchestrates the individual executables of the earth system components via a communication library. This approach is less invasive for existing codes and requires only the insertion of communication calls without the need to fit into a common framework. The initial performance bottleneck in OASIS3 (Valcke, 2013) has been relaxed with the inclusion of the Model Coupling Toolkit (MCT; Larson et al., 2005; Jacob et al., 2005) in the OASIS3-MCT coupler (Valcke etl al., 2015; Craig et al., 2017). MCT parallelizes the regridding between different earth system components and the necessary communication.

The hierarchical approach with individual models as entities of a framework is typical for ESMs where the different components are developed within one institution. With MOSSCO (Lemmen et al., 2018) there is also an example of coupled model development in the Baltic Sea region that uses ESMF to build a regional ESM with a focus on coastal processes in the North Sea and Baltic Sea. The Modular Earth Submodel System (MESSy; Jöckel et al., 2010) originated in the need for atmospheric chemistry being coupled to atmospheric dynamics and has evolved into a system with a coupled regional atmosphere component COSMO (Kerkweg et al., 2018).

Most other efforts in coupled atmosphere-ocean modeling in the Baltic Sea region are based on the use of community models that are coupled with the community OASIS coupler (Tab. 2.2.3.1). The advantage is that specific development tasks can be distributed to different communities and individual groups benefit from each other's expertise.

Traditionally, sequential coupling has been used and has the advantage that component models update the variables and fluxes with the most recent information from other coupled components. On the other hand a sequential coupling is less efficient, since other components need to wait until the active component has updated its state. Nowadays concurrent coupling is preferred where all coupled components run concurrently with state variables and fluxes that have been updated commonly during the last coupling time step. This implies that the coupling time step between coupled components needs to resolve the important processes that lead to feedbacks between e.g. atmosphere and ocean. A typical example would be the moisture flux in a RCM to investigate monsoon dynamics (Yang et al., 2019), the generation of medicanes (Akhtar et al., 2014) or coastal upwelling (Perlin et al., 2016).

A long known issue with coupled modeling is the mismatch of land-sea masks between atmosphere and ocean components of a coupled system (Jones, 1999). The Baltic Sea region is especially prone to this issue with the complex coastlines and so far a relatively low resolution of 0.11 to 0.22 degrees in

875 the atmosphere models and 1/60 to 1/20 degree in the ocean models. With higher resolution of convection-permitting regional climate models (CPRCMs) approaching the resolution of Baltic Sea models (Belusic et al., 2019) the effects might become less prominent, but the conceptual issue remains. One way to deal with ambiguous assignment of grid cells is the remapping be carried out on an exchange grid that is the joint set of grid cells between two participating grids (Balaji et al., 2005,
880 Bauer et al., 2020). The exchange grid also addresses the vertical flux between different model components but has so far not yet been used in RCMs of the Baltic Sea region.

Comparing coupled and uncoupled ocean model runs usually involves simulations that use different bulk formulae to calculate air sea fluxes in the atmospheric boundary layer in the coupled and
885 uncoupled modes, respectively (e.g. Dieterich et al., 2019b). To separate the effect of coupling from other differences between coupled and uncoupled models this needs to be addressed in more detail in future efforts. Nevertheless, many studies aimed at demonstrating improvements in simulating aspects of the present day climate. However, a general statement about model performance of coupled versus standalone models can not be drawn as many studies showed added value of coupling especially in
890 those cases when the uncoupled model was driven by low quality forcing data (Tian et al., 2013; Gröger et al., 2015; Ho-Hagemann, 2017). Furthermore, andand the uncoupled models often had a lower resolution at the air sea boundary. In turn, this implies the application of coupled models in particular in future climate projections as global climate models can have large biases and constraints of the governing model that drive the uncoupled model may be too tight (Mathis et al., 2018).

895 ## 2.3 Ocean-wave-atmosphere coupling

One major characteristic of the atmosphere - ocean interface is the presence of surface gravity waves, the surface changes as a direct response to the atmospheric forcing. Surface gravity waves (hereafter designated waves) are mainly generated by the wind; the wave field is thus strongly dependent on the wind field. For coastal areas, the over-water fetch is one additional aspect. Waves are characterized by
900 a variety of properties (wave height, wave age, wave steepness, etc). The transport of momentum is the key property, but waves also influences the exchange of heat and mass, as well as the turbulence of the lower atmosphere and the upper ocean. Indirectly, the wave influences can affect the whole boundary layer/mixed layer in the atmosphere as well as the ocean.

As a buffer role at the air-sea interface, waves can be divided into growing waves (young waves) and
905 decaying waves (swell) with very different impacts on the atmosphere and the ocean. Waves extract energy from the air-side stress when waves are growing. By contrast, they release momentum to the ocean in the presence of decaying waves. When considering the role of waves, the stress balance at the air-sea interface is expressed as (ECMWF, 2017),

$$\tau_a = \tau_{oc} + \tau_w + \tau_{ds} \text{ (1)}$$

910 where τ_a is the air-side stress, τ_{oc} is the ocean-side stress, τ_w is the wave-induced stress, and τ_{ds} is the momentum flux from the wave field to mean currents. In traditional stand-alone or atmosphere-ocean coupled models, τ_a is identical to τ_{oc} without considering the role of waves. It has, however, been shown that the normalized ocean-side stress, τ_{oc}/τ_a, can be larger (smaller) than 1.5 (0.85) in the Baltic and the North Seas (Alari et al.,2016; Wu et al.,2019b; Qiao et al., 2021).

915 For high wind speed conditions sea spray and airflow separation caused by breaking waves are important aspects. It leads to the level off of the drag coefficient under extreme winds (about 25-30 m/s for the mean wind speed at 10 m). For swell conditions, the air-wave interaction is more complex and waves influence the momentum flux, the turbulence of the atmosphere as well as the mixing (Nilsson et al., 2012; Wu et al., 2017a).

920 Wave breaking can transfer a significant amount of energy flux into the ocean (Melville et al., 2002), which mainly affects a down to few significant wave height depths from the ocean surface (D'Asaro, 2014). The breaking-wave-induced energy flux is commonly parameterized as an additional input of turbulent kinetic energy (TKE), $\alpha_{CB} u_{\square}^3$, in the surface boundary (Craig and Banner, 1994), where $u_{\square}$ is the ocean-side friction velocity and α_{CB} is a wave-related parameter which is usually treated as a
925 constant (e.g., 100) without considering the impact of wave status.

Due to the periodic motion, waves induce a net drift in the wave propagation direction ($u_s = u_L - u$, the difference between the Eulerian velocity, u, and Lagrangian velocity, u_L), which is defined as Stokes drift (Stokes, 1880). The Stokes drift can impact on the wave-averaged momentum equation through the Coriolis-Stokes force (CSF), the vortex force and a Stokes-corrected pressure (e.g. Suzuki
930 and Fox-Kemper, 2016):

The CSF can alter the ocean Ekman transport, which is indicated by numerical simulations (Polton et al., 2005). The Langmuir turbulence (LT) induced by the vortex force is one of the most important wave-related processes, which can indirectly affect the whole mixed layer through the turbulent transport of the wave-induced turbulence (Belcher et al., 2012). Many turbulent closure schemes have
935 been modified in order to implement the LT influences (Ali et al., 2019), such as, K-Profile Parameterization turbulence scheme (McWilliams and Sullivan, 2000), $k - \epsilon$ turbulence model (Axell, 2002), etc. The Stokes-corrected pressure is small in the order of the Rossby number and can be neglected in coarse resolution models. In addition, the Stokes drift can also affect the mass and tracer transport through the divergence of the sea-surface height and tracer advection, respectively
940 (McWilliams and Sullivan, 2000; Wu et al.,2019b).

Nonbreaking-wave-induced ocean mixing proposed by Qiao et al (2004) and Babanin and Haus (2009) is a direct stirring function in the ocean by waves. In the coastal areas, the wave-induced bottom stress can also affect the circulation and sea water level (Davies and Lawrence, 1995).

In marginal ice zones, short waves are attenuated rapidly by ice and long waves can propagate much
945 further into the ice areas. Wave radiation stress on the ice is a term usually neglected in the ice model. The mechanism of the wave-ice interaction is complex, more detailed description of the wave-ice interaction as well as their parameterization in models refer to Zhao et al. (2015) and Squire (2018).

2.3.1 Effects on the coupled system when introducing waves

950 To capture the wave-current and wave-atmosphere interaction, several models coupled with a wave model have been developed in the Baltic Sea and the North Sea region. The wave model has been coupled to regional climate models, i.e., RCA-WAM (Rutgersson et al., 2012; Wu et al., 2015) and COSMO-WAM (Wahle et al., 2017), and weather prediction models, i.e., WRF-WAM (Wu et al., 2017b) and WRF-SWAN (Larsén et al., 2019). On the ocean side, several wave-ocean coupled
955 models have been tested: one-way coupled model, such as NEMO-WAM (Alari et al., 2016; Wu et al., 2019b; Staneva et al., 2017), two-way coupled model GETM-WAM (Staneva et al., 2016). Recently, a three-way coupled atmosphere-wave-ocean system (Uppsala University-Coupled Model, UU-CM) was developed and tested in the Baltic Sea region (Wu et al., 2019a).

Storm simulations

960 The wave feedback on the atmospheric simulation is significant under young waves since they extract more momentum for their growth (Janssen and Viterbo, 1996). Accordingly, wave coupling is more important under extreme conditions (young wave dominating). Based on the simulation of 23-year storms using WRF-SWAN model with a domain covering North and Baltic Sea, Larsén et al. (2019) found that the wave influence improves the model performance compared with the uncoupled model

965 (mainly under high wind range).

Sea spray under high winds can significantly impact the momentum and heat flux ~~in~~at the air-sea interface. An effective roughness length parameterization considering sea spray influences was developed by Wu et al. (2015) based on the studies of Kudryavtsev and Makin (2011); Zhao et al. (2006). Together with the heat flux parameterization considering sea spray (Andreas et al., 2015), the
970 parameterizations were implemented into the RCA-WAM coupled model for storm simulations (Wu et al., 2015). The results have shown that the sea spray impact on the wind stress can significantly improve the wind simulation during storms, in addition the sea spray impact on the heat flux improves the temperature simulation.

The storm-induced surge has been investigated using ocean-wave coupled systems. Wave-current
975 interaction processes were implemented in the GETM-WAM model which include radiation stress, Stokes drift, bottom friction modification, and turbulent kinetic energy due to wave friction (Staneva et al., 2016). They found that the coupled system does not have a significant influence over the open North Sea, however, it significantly improves the simulation in the coastal areas in terms of significant wave height, water level, and current. In the recent study by Staneva et al. (2017), the CSF,
980 sea-state-dependent momentum and energy flux were implemented in the NEMO model with external wave forcing data. The simulation of two storms in the North Sea indicates that the wave-related processes improve the storm surge simulation in extreme conditions. Compared to the other wave-related processes investigated in their study, the sea-state-dependent momentum flux plays a dominating role which agrees with the results of Wu et al. (2019b).

985 *Mesoscale features*

Coastal upwelling occurs frequently in the summer months ~~of~~in the Baltic Sea, which is mainly induced by the divergence (convergence) of the wind stress (Lehmann and Myrberg, 2008). Ocean waves affect the coastal upwelling through altering the ocean-side stress (Eq. 1) and upper-ocean mixing (mainly through CSF and breaking wave-induced energy flux). Based on an offline wave-
990 ocean coupled model, Alari et al. (2016) found that the ocean model better captures the distribution of the sea surface cold water induced by a coastal upwelling event in the eastern coast of the Baltic Proper. In their study, three wave-related processes were implemented in the ocean model, i.e., CSF, sea-state dependent energy and momentum flux. With a similar ocean model set up in the Baltic and the North Sea area, Wu et al. (2019b) investigated the wave impact on the Baltic Sea coastal
995 upwelling in terms of intensity and frequency during June to September in 2015. In addition to the three processes investigated in Alari et al. (2016), the Stokes drift impact on the mass and tracer advection was also included in their model. They found that the Stokes drift impact on the mass and tracer advection largely cancelled the influence of CSF on the coastal upwelling simulation. Compared with the control experiment (without wave related processes), the simulation including the
1000 four wave-related processes changes the upwelling frequency up to 10% which varies with location (Fig. 7). And the combined effect of those wave-related processes increases the weak upwelling frequency ($-4 < \Delta T < 2.5 \circ C$) but decreases the strong upwelling frequency ($\Delta T < -6 \circ C$), here (ΔT) is the SST difference from the zonal mean temperature (Wu et al., 2019b).

Fig. 7: The left column shows the upwelling frequency during June to September, 2015, the right column shows the difference between the simulation considering wave influence and the control experiment (Figure is adapted from Wu et al., 2019b).

Two convective snow band cases in the Baltic Sea region were investigated using the RCA-WAM model by Jeworrek et al. (2017). Due to the wave feedback on the atmosphere through changing the sea surface roughness length, the RCA-WAM model processes a time shift of several hours in the maximum 10 m wind simulation. In the simulation of those two convective snow cases, the wave coupling has less influence than that from the ocean coupling (see above).

Climate simulations

The swell impact on the atmospheric mixing was introduced into the RCA-WAM regional climate model through adding an extra wave-age dependent coefficient to the mixing length (Rutgersson et al., 2012). Simulations show that the swell impact on the atmospheric mixing can alter the mean surface wind up to 0.3 m/s in the Baltic Sea and the North Sea (Rutgersson et al., 2012; Wu et al., 2016). The magnitude and direction of the change depend on the wave field and environmental conditions (Rutgersson et al., 2012; Wu et al., 2016).

Based on a three summer month simulations, Alari et al. (2016) found that the wave-related processes (sea-state dependent momentum flux, TKE induced by wave breaking, and Stokes-Coriolis forcing) can change the sea surface temperature up to 1 degree in the Baltic Sea, in which, the sea-state dependent momentum and TKE flux play anda warming role but Stokes-Coriolis forcing plays a

cooling role along coastlines. Similar to the sea surface temperature, the Stokes-Coriolis forcing
1025 dominates the bottom temperature cooling along coastlines where the water depth is relatively
shallow. However, in their study, the LT influence was not included in the model.

Recently, Wu et al. (2019a) developed a fully coupled atmosphere-wave-ocean coupled model with an
improved representation of the air-wave-sea interaction processes. Based on two month-long (January
and July, 2015) simulation, they found that the coupling has a significant impact on coastal areas in
1030 the Baltic Sea. The wave-current interaction has a larger influence ~~on~~in the summer month~~s~~ than in
winter month~~s~~ (Wu et al., 2019a) which is because the wind speed is higher in winter and sea-state-
dependent momentum/energy flux and the Stokes drift related processes are more important for
upper-ocean mixing.

1035 ## 2.4 Hydrological coupling - Closing the water cycle

In coupled system modeling, hydrological coupling usually refers to the closure of the water cycle
between land and ocean via the interactive simulation of river runoff. River runoff is an important
component of global and regional water cycles, especially in the Baltic Sea catchment where it
comprises about one half of the precipitation over land areas (Lind and Kjellström, 2009), and about
1040 twice as much as the precipitation over sea areas (Jacob, 2001; Leppäranta and Myrberg, 2009).
Freshwater inflows from runoff and precipitation affect the thermohaline circulation (Knudsen, 1900;
Placke et al., 2020). Decadal variations in Baltic Sea salinity are caused largely by the accumulated
runoff to the Baltic Sea (Meier and Kauker, 2003; Väli et al., 2013; Radtke et al., 2020). On the one
hand, the thermohaline circulation of the Baltic Sea is also influenced by inflows of highly saline
1045 water from the North Sea (that itself may be strongly impacted by precipitation and river runoff,
Lehmann and Hinrichsen, 2000). On the other hand, river runoff into and net precipitation over the
Baltic Sea mainly induce its outflow into the North Sea where it is an important source of
stratification in the North-Western European Shelf (Hordoir and Meier, 2010).

In addition, river runoff and the associated nutrient loads substantially influence the functioning of the
1050 marine ecosystem. These inflows from land, carrying fresh, nutrient-rich water determine coastal
physical conditions and nutrient concentration. Therefore, they dominantly influence primary
production and affect the variability of the whole ecosystem (e.g. Gustafsson et al., 2012; Daewel and
Schrum, 2017). In the Baltic Sea, this becomes even more relevant as the Baltic Sea is almost
decoupled from the open ocean so that land-borne nutrients significantly contribute to determining
1055 ecosystem productivity (Thurow, 1997; Österblom et al., 2007).

Consequently, river runoff is also an important component for the coupled system modeling over the
Baltic Sea region. Hagemann et al. (2020) provide an overview on the current state of high resolution
modeling of river runoff (or discharge) within the framework of regional coupled system models
(RCSM). Note that the present section 2.4 comprises excerpts and, hence, some overlap with the
1060 introduction section of Hagemann et al. (2020) as the associated information is relevant to the present
review. In addition to traditional regional climate models (RCMs), RCSMs have been recently
developed to conduct climate change studies at high spatial and temporal resolutions. In order to
adequately represent biogeochemical cycles, a proper description of the transport of, e.g. nitrogen,
phosphorus, carbon, and silicon, into the ocean requires a very detailed representation of stream
1065 characteristics (such as flow paths, lakes, ponds, reservoirs, wetlands and floodplains) because the
smallest water bodies may exhibit large parts of the retention on land (Bouwman et al., 2013).
Therefore, RCSMs require a high-resolution discharge component to couple their atmosphere/land
components to the ocean component and to adequately resolve smaller catchments and the day-to-day
variability of discharge.

Coupling to coarse resolution discharge models

The current discharge models applied in coupled (or earth system) models for global or regional climate simulations usually do not fulfill this requirement. In global ESMs, discharge (or routing) models are frequently part of the coupled system (often as part of the land surface scheme) but their spatial resolution is usually 0.5° (Roeckner et al., 2003; Guimberteau et al., 2012) or coarser (Lawrence et al., 2011; Milly et al., 2014; Best et al., 2011).

Instead of using hydrological coupling, many RCSMs use prescribed runoff, taken either from climatology, observations or model data. For example, Gröger et al. (2015) coupled the Rossby Centre regional Atmospheric climate model RCA4 on a 24 km European domain with the NEMO ocean model over the Baltic Sea and North Sea, but river runoff was prescribed as a daily climatology of an E-HYPE ERA-interim hindcast (Donnelly et al., 2016). To reflect the projected increase in precipitation in the northern part of the Baltic Sea (e.g., Donnelly et al., 2014), in the Bothnian Sea and Bothnian Bay a linearly increasing discharge to +10% in 2100 is used. Thus, only a few RCSM setups exist where a discharge model is included, but its resolution is rarely higher than 0.5°. Examples comprise the Hydrological Discharge (HD) model (Hagemann and Dümenil, 1998) at 0.5° (Sein et al., 2015; Sitz et al., 2017; Elizalde, 2011), TRIP (Oki and Sud, 1998) at 0.5° (Dell'Aquila et al., 2012; Sevault et al., 2014) and LARSIM (Bremicker, 2000) at 1/6° over Northern Europe (Lorenz and Jacob, 2014).

The latter is part of the fully coupled RCSM BALTIMOS for the Baltic Sea and links the atmospheric RCM REMO to the Baltic ocean/sea ice model BSIOM. Lorenz and Jacob (2014) introduced the BALTIMOS system and showed first results from a simulation driven by analysis data from the European Centre for Medium Range Weather Forecast (ECMWF). Sein et al. (2015, 2020a) introduced the RCSM ROM in which the global ocean-sea ice-marine biogeochemistry model MPIOM/HAMOCC with regionally high horizontal resolution is coupled to the atmospheric RCM REMO and the global HD model (see above) via the OASIS coupler. They used forcing from NCEP/ NCAR reanalysis and ECHAM5/MPIOM (Roeckner et al., 2003; Jungclaus et al., 2006) historical simulations and evaluated their results for the North Atlantic and North European region, where they also specifically addressed the Baltic Sea catchment.

Coupling to high resolution discharge models

Several studies exist where a RCM was coupled to a very-high resolution regional hydrology model that covers the full range of processes at the land surface. As such coupled systems are often limited by computational effort, currently these studies cover only short periods or relatively small catchments/areas (e.g. Mauser and Bach, 2009; Senatore et al., 2015; Shrestha et al., 2014). Larsen et al. (2014) presented results from a full two-way coupling of the HIRHAM RCM over a 4000 km × 2800 km domain at 11 km resolution and the combined MIKE SHE-SWET hydrology and land-surface models over the Danish Skjern River catchment (area: 2500 km^2).

Over Korea, the discharge model TRIP has been coupled to a RCM at 0.5°, 0.25°, and 0.125° in preparation of future RCMS studies (Lee et al., 2015). Nguyen-Quang et al. (2018) used a high-resolution (1 km) river network to define hydrological transport units within the grid boxes of the Orchidee land surface model and applied this over the Mediterranean region using forcing data at 0.5° and 0.25° resolution. To our knowledge, none of the hydrological models used in the studies listed above and by Hagemann et al. (2020) has been used in a fully coupled RCSM setup that can be applied for climate time scales and large-scale areas.

Very recently, Hagemann et al. (2020) developed a high-resolution version of the HD model that is globally applicable at 5 Min. resolution (HD5 model). In their study, offline HD5 model results were

evaluated over Europe and the Baltic Sea catchment. In order to prepare high-resolution scenario simulations over Europe and the Baltic Sea, the HD5 model has already been coupled within GCOAST (Geesthacht Coupled cOAstal model SysTem), which is the RCSM developed at the Helmholtz-Zentrum Geesthacht. This coupling is necessary to ensure that the simulated discharge and other hydrological variables are consistent with the climate variables so that interactions between the different compartments of the regional earth system can be considered. Ho-Hagemann et al. (2020) introduced a GCOAST subset in which OASIS3-MCT couples the atmospheric RCM CCLM over the 0.11° EURO-CORDEX domain, the HD5 model over Europe, and the ocean-sea ice model NEMO-LIM3 over the Baltic Sea, North Sea and parts of the North Atlantic. Using this GCOAST-AHOI subset, they investigated the effects of air-sea coupling on internal variability of the regional atmospheric model.

Hydrology models in future climate scenarios

The aforementioned sensitivity of the Baltic Sea to yearly freshwater input implies that any coupled hydrology model needs to be very accurate in simulating the total yearly discharge over the catchment area. Consequently, the use of regionally coupled hydrology models in future climate scenarios is challenging because on the one hand the water cycle in coupled general circulation models (GCMs) is often not closed (Liepert and Lo, 2013). On the other hand, GCMs and RCMs suffer from substantial biases, especially with regard to precipitation and the hydrological cycle (Flato et al., 2013; Kotlarski et al., 2014), which affect the simulated discharge. An example comes from the regionally coupled atmosphere-ocean-sea ice-marine biogeochemistry model ROM (Sein et al., 2015) which overestimates catchment precipitation by 11-14% translating into a 23-34% overestimation in discharge when driven with different reanalysis datasets. Thus, current studies using future scenarios for the Baltic Sea mostly rely on rough estimates of increasing discharge in the Bothnian Bay and the Bothnian Sea by 10% in 2100 (Dieterich et al., 2019, Gröger et al. 2019) or use discharge data from uncoupled hydrology models (Saraiva et al., 2019a, 2019b; Meier et al., 2018; Meier et al., 2019a, 2019b). By contrast, the use of the online-coupled HD component is physically more consistent as the water cycle is closed but may transfer biases from the atmosphere/land components into the ocean, leading, e.g., to an extraordinary strong freshening in future scenarios (Sein et al. 2020a).

3. Uncertainties and gaps

LAND-ATMOSPHERE

Previous works have shown the potential for substantial land-atmosphere coupling in the Baltic Sea region, through land use change, natural vegetation dynamics and land management. RESMs that downscale CMIP6 outputs to the Baltic Sea region should, as a first step, use land use/management scenarios consistent with CMIP6 protocols, i.e. from the LUH2 dataset (Hurtt et al. 2020). Simulations with RCA-GUESS, RCAO-GUESS (Zhang et al. 2020) and other RESMs have shown the importance of and potential for land-atmosphere-ocean interactions in the Baltic Sea region. Coupling new earth system components is expected to further advance our understanding of climate and environmental change in the Baltic Sea region. These include land-ocean/freshwater interactions, including the leaching of carbon and nutrients from land, the use of simulated BVOC (Kulmala et al. 2014; Hantson et al. 2017) and aerosols precursor from natural and managed vegetation and wildfires, CH4 and N2O emissions from wetlands and agriculture.

1160

With respect to coupled atmosphere-ocean modeling the choice of the size of the coupled domain has always to be carefully considered and in most cases the economical costs to drive the model, sets an upper limit. When the atmosphere domain covers several seas as it does in Euro-CORDEX domain it might be feasible~~fieasible~~ to coupled only a few of them to save computational~~conputational~~ costs

1165 (e.g. Tian et al., 2013; Gröger et al., 2015). However, with respect to regional ocean studies it appears reasonable to avoid lateral boundaries too close to the shelf break as there important small scale processes take place determining the shelf-open ocean exchange as demonstrated for the North Sea (Gröger et al., 2013) that benefit from high resolution. On the other hand, including slower components with longer internal timescales like parts of the open North Atlantic will allow the

1170 regional model to generate its own long time internal variability and which is likely out of phase with the decadal variation of the driving global model. One example is provided by Sein et al. (2014) who emphasized in simulations for the Arctic Ocean that inclusion of the North Pacific in coupled domain destroys interannual correlation with reanalysis data. Hence, special nudging techniques might be necessary to adapt the regional ocean model large scale circulation to that of the driving global ocean

1175 model as this is practiced for atmospheric regional models (von Storch et al., 2000).

Along the coastal zone small scale oceanic processes like upwelling can build up strong SST gradients along the coasts further influencing land sea atmosphere dynamics. However, SST patterns are still strongly smoothed while communicated to the atmosphere as the SST field is interpolated onto the

1180 atmosphere grid. Thus, more advancements for coastal zone dynamics can be expected from higher resolution of atmosphere models up to a few kilometers together with the transition to convection permitting models instead of hydrostatic models. With respect to future scenario climate simulation more research is necessary to assess whether or not the coupled and uncoupled models reveal different climate changes signals in scenario simulations in both the hydrographic and atmospheric properties

1185 of the Baltic Sea region. First attempts to address this question have been made (e.g. Gröger et al., 2021, Bøssing Christensen et al., 2021; Meier et al., 2021).

WAVES

Adding surface waves to a coupled system is becoming more important with increasing resolution, in

1190 particular, when detailed information is required in complex areas (such as for off-shore wind energy applications in the coastal zone). It has also been shown that wave information improves the description of the ocean mixing. There is, however, still limited knowledge concerning the impact of waves on the exchange of heat and mass. The interaction between waves and ice is also not well described in present models, which induces uncertainties in the freezing of ice as well as the wave

1195 properties in the marginal ice zone. This is important in polar regions, but also potentially in the northern Baltic Sea.

For extreme events (often linked to local-mesoscale systems) high resolution models are crucial, and introduction of as accurate information of the earth system as possible is essential. For this, coupling to other high resolution models is a prerequisite. This includes primarily atmosphere, ocean and

1200 waves, but can be expected to also be beneficial with submodels for ice, aerosols and etc. Improvements by including wave models into regional earth system models can thus be expected in particular for features like convective precipitation, cold-air outbreaks, lake-snowfall, polar lows and mid-latitude storms.

1205 Socio-economic development is a major driver for nutrient loads into the Baltic Sea (Arheimer et al., 2012; Bartosova et al., 2019) that contribute to eutrophication and hypoxic conditions (e.g. Saraiva et al., 2019a, 2019b). So far, only a few hydrological models include nutrient cycling to provide explicit estimates of nutrient inputs to the sea (Hundecha et al., 2016). This needs to be addressed in more detail in future model development. Hence, a major challenge is to include/combine 1) land use

1210 change, 2) terrestrial carbon and nutrient cycling from fertilizers, 3) dynamic vegetation modeling and 4) long-term storage of nutrients in the soils.

The potential increase in weather extremes will have an effect on soil erosion and nutrient loads which is a topic which has not yet been implemented in hydrological models. This is especially important in the context of future climate change when some extreme conditions may become more

1215 frequent (e.g. Jacob et al., 2014). For the adequate representation of biogeochemical cycles, the hydrological model must not only consider the respective lateral transports, but it must also include detailed biogeochemical process descriptions (e.g. Tang et al. 2018).

However, even with a coupled hydrological component, human impacts and their future developments are currently not regarded in coupled models of the Baltic Sea region. Here, many rivers are strongly

1220 affected by human impacts such as water abstractions, e.g. for irrigation, and regulation, e.g. by dams. Consequently, for the modeling of rivers and watersheds that are highly influenced by human activities, related processes need to be implemented into the respective hydrological model component. As pointed out by Hagemann et al. (2020), this includes the implementation of existing and planned dams and reservoirs (based on available global databases), their management of river

1225 flow regulations as well as modules to simulate water withdrawals, e.g. for irrigation. Apart from prescribed scenarios, the future development of these impacts might be realized with simple economic modules.

INTERNAL VARIABILITY

Hydrodynamical earth system components, i.e. ocean and atmosphere primitive equation models are

1230 characterized by generating noise as a result of turbulent dynamics (e.g. Weisse et al., 2000; Penduff et al., 2018; Wiese et al., 2020; Geyer et al., 2021). In climate applications where usually long term averages and statistics are considered this is no problem provided that the averaging period largely exceeds the frequencies of internal variability of the system. It is neither problematic if short term events are analyzed, provided that only the statistics of these events over an appropriate long period is

1235 interpreted. Contrary to this, i.e. when single events are analyzed like e.g. the timing of certain storms (e.g. Ho-Hagemann et al., 2017, 2020) or wind induced coastal upwelling events in the Baltic Sea. In these cases the model solution can be substantially modulated by internal variability and so the comparison of coupled vs uncoupled systems may be misleading. In turn, this requires a profound estimation of the robustness of the model solution with respect to the initialization, boundary

1240 conditions (Weisse et al., 2020; Ho-Hagemann et al., 2020) and even the computing platform (Geyer et al., 2021). For this, different methods have been developed mainly based upon the generation of large ensembles taking into account small perturbations in the initialization (e.g. Giorgi et al., 2000; Weisse et al., 2000; Weisse et al., 2003; Sieck and Jacob, 2016).

Comparing ensembles of coupled and uncoupled regional ocean atmosphere models Ho-Hagemann et

1245 al. (2020) has been recently demonstrated that interactive air sea coupling can substantially reduce internal model variability compared to uncoupled atmosphere models. In case of the storm Christian occurring from 27 to 29 October 2013 in northern Europe the authors found that the larger uncertainty in the atmosphere-only simulation was caused by a combination of two factors: (1) uncertainty in parameterization of cloud-radiation interaction in the atmospheric model and (2) lack of an active

1250 two-way air-sea interaction.

In a similar approach of Ho-Hagemann et al. (2020), Wiese et al. (2020) also found the reduction of internal model variability in ensembles of an interactive atmosphere-wave coupled model compared to those of a stand-alone atmospheric model. The role of internal variability is still not sufficiently investigated in more complex coupled systems involving more components like e.g. fully coupled

1255 ocean-wave-atmosphere models as pointed out by Wiese et al. (2020) or coupled ocean-atmosphere-land vegetation models.

OTHER COMPONENTS

For the current generation of RCMs a substantially lower projected 21st century warming compared

1260 to their driving global models has been demonstrated and the neglection of scenarios for time varying aerosols~~aerosoles~~ has been identified as a key process (Boé et al., 2020). However, the use of explicit atmospheric chemistry and transport models as interactive parts within global earth system models is still not common and is mostly parameterized in CMIP6 models (Stevens et al., 2017; Fiedler et al., 2019). Thus, the representation of aerosoles is a major challenge in RCMs and has been recognized

1265 within the CORDEX Flagship Pilot Study (FPS-Aerosol https://www.hymex.org/cordexfp s-aerosol/ wiki/doku.php?id=start).

Despite the advancements in including the biophysical feedback from the land vegetation as outlined in section 2.1, analogous feedbacks from the marine biogeochemical cycles on the physics are so far

1270 not implemented in RCSMs. The main feedback is due to the altered penetration of solar insolation by marine biota that further influence heat absorption and thus the vertical distribution of heat (Lengaigne et al., 2009). Regional studies for the Arctic (Lengaigne et al., 2009) and for the Indian Ocean (Sein et al., 2020b) suggest that intense phytoplankton blooms strongly influence vertical mixing and thermocline dynamics. The latter two processes are essential for the Baltic Sea especially

1275 in the context of projected increases of cyanobacteria blooms in a future warmer climate (e.g. Saraiva et al., 2019a; Saraiva et al., 2019b; Meier et al., 2019a; Meier et al., 2019b).

4. Conclusions and key messages

1280 For the Baltic Sea region previous research identified a number of important feedback loops between earth system compartments that alter both the mean climate as well as extreme event statistics such as heavy precipitation, storms and flooding. Regional earth system modeling is the only way to represent feedbacks between different earth environmental compartments in an adequate way (Heinze et al., 2019).

1285

The coupling of atmosphere models to dynamical components for the ocean and land constitutes a major step towards earth system modeling of the Baltic Sea region. Climate projections for the Baltic Sea region up to the end of the century reveal that the feedback of vegetation changes on climate warming is mostly negative in North and central Europe while an amplification of warming up to 1 K

1290 is obtained for southern Europe (Wramneby et al., 2010). Likewise, implementation of scenarios for land management in the Baltic Sea region can alter temperature locally to up to a few Kelvin (Strandberg and Kjellström, 2019). The alterations emerge from a number of coupled land-atmosphere processes involving biophysical feedbacks such as changes in albedo and roughness length and evapotranspiration and related changes in LAI and vegetation-type as well as biochemical

1295 feedbacks from high carbon dioxide concentration.

Unlike the land surface where evaporation depends also on precipitation with a further effect on heat exchange, freshwater supply to the ocean (via runoff and precipitation) has no direct influence on evaporation over sea. Accordingly, coupled atmosphere ocean model studies mainly identified
1300 thermal air sea coupling as most significant (e.g. Kjellström et al., 2005; Gröger et al., 2015; Ho-Hagemann, 2017;Gröger et al., 2021) with the predominant impact on simulated SSTs. For the Baltic Sea deviations between prescribed SST and sea ice fields and modelled quantities can add up to a few Kelvin (Tian et al., 2013; Gröger etal., 2015). In turn, good quality SST fields appear a prerequisite for the representation of extreme events over land such as convective snowbands, heavy precipitation,
1305 or flooding due to the influence of SST and the presence/absence of sea ice on the large-scale atmospheric circulation. Many studies demonstrate the importance of interactive wave coupling in mediating the atmosphere-ocean exchange of heat, momentum and mass which enables to more reliably resolve processes such as the effect of breaking waves otherwise parameterized in either ocean or atmosphere models..
1310

The first fully coupled atmosphere-ocean-hydrology models for the Baltic Sea region have been accomplished (Sein et al., 2015; 2020; Hagemann et al., 2020) and are an important step towards the closure of the water cycle. However, they likewise elucidate common problems related to strong biases in input precipitation/evaporation. Without bias correction this leads to unrealistic river runoff
1315 to the Baltic Sea (Sein et al., 2020). This is in particular problematic for the Baltic Sea where runoff constitutes a major contribution to the halocline structure and the freshwater budget. On the road to

Many studies aim at demonstrating added value of interactive coupling by direct comparisons of single variables between coupled and uncoupled models. However, this may be misleading as in many
1320 cases, these improvements simply reflect bad quality of prescribed boundaries used in the stand alone model (see, e.g., Gröger et al. 2015). This has implications for downscaling the effect of future climate changes because global models can be strongly biased on the regional scale and thus provide bad quality input data (the so called "rubbish in rubbish out problem", e.g. Hall, 2014). Here, the more complex regional coupled models can develop more independently from the parent biased global
1325 model by generating its own climate as demonstrated by Mathis et al. (2018).

Finally, coupled models can be computationally highly demanding especially when multiple components are included. For hindcast simulations of the historical climate the more economic standalone models are a good tool provided that forcing and boundary data is of good quality. For
1330 future climate simulations where this is not the case, rather coupled models will be the first choice. The higher costs of coupled climate simulations will require to reduce the size of individual ensemble simulations which hampers a robust assessment uncertainties due to global models and scenarios. However, advanced techniques for reducing the ensemble size by by conserving the model ensemble spread are currently under development (e.g. Wilcke and Bärring, 2016).
1335

Author contributions. WH and PM wrote the section about land biosphere coupling, HTMHH, HEMM, CD, MG wrote the section about ocean atmosphere coupling, AR and LW wrote the section about atmosphere ocean wave coupling, SH and CD wrote the section about hydrology coupling, and JH and JJ wrote the section about atmosphere ice ocean coupling. The sections of conclusions,
1340 uncertainties and gaps represent the joint effort of all authors. The final manuscript was compiled by MG.

Competing interests. The authors declare that they have no conflict of interest.

Code/Data availability. The review paper uses exclusively published data. We refer to the referenced literature and corresponding authors for reasonable requests.

Acknowledgements

1345

PAM and WM were supported by the FORMAS Research Council (grant number 2017-01895) as part of the National Research Programme on Climate. It is a contribution to the strategic research areas MERGE (http://www.merge.lu.se) and BECC (http://www.becc.lu.se), both hosted by the Centre for Environmental and Climate Research (http://www.cec.lu.se) at Lund University, Sweden.

1350

CD was supported by the ClimeMarineand EDUCAS projects, funded by the Swedish Research Council Formas within the framework of the National Research Program for Climate (Grant no. 2017-01949 and 2019-00829). Additional support came from the JPI-Climate initiated ERA4CS project Co-CliME, co-funded by the European Union (Grant 690462).

1355

HTMHH was supported by the CLM-community and the German Climate Computing Center (DKRZ), and funded by the German project REKLIM (https://www.reklim.de).

LW was supported by FORMAS Research Council (grant number 2017-00516)

1360

SH was partially supported by the Initiative and Networking Fund of the Helmholtz Association through the project "Advanced Earth System Modelling Capacity (ESM)" (https://www.esm-project.net).

AR was supported by FORMAS (grant number 2018-01784).

1365

JH has been supported by the Strategic Research Council at the Academy of Finland, project SmartSea (grant number 292 985).

References

1370 Akhtar, N., Brauch, J., Dobler, A., Béranger, K., and Ahrens, B.(2014): Medicanes in an ocean–atmosphere coupled regional climate model, Nat. Hazards Earth Syst. Sci., 14, 2189–2201, https://doi.org/10.5194/nhess-14-2189-2014

Akhtar, Naveed, Krug, Amelie, Brauch, Jennifer, Arsouze, Thomas, Dieterich, Christian, Ahrens, Bodo:
1375 European Marginal Seas in a regional atmosphere-ocean coupled model and their impact on Vb-cyclones and associated precipitation, Clim Dynam, 2019, 1-33, 10.1007/s00382-019-04906-x, 2019

Alari, V., Staneva, J., Breivik, Ø., Bidlot, J.R., Mogensen, K., Janssen, P., 2016. Surface wave effects on water temperature in the baltic sea: simulations with the coupled nemo-wam model. Ocean Dynamics 66, 917–930.
1380
Aldrian, E., Sein, D. V., Jacob, D., Gates, L. D., & Podzun, R. (2005). Modeling Indonesian rainfall with a coupled regional model. Climate Dynamics, 25, 1–17. Retrieved from http://www.baltex-research.eu/RCM2014/Material/IBESPS_No.3_low.pdf.

1385 Ali, A., Christensen, K.H., Breivik, Ø., Malila, M., Raj, R.P., Bertino, L., Chassignet, E.P., Bakhoday-Paskyabi, M., 2019. A comparison of langmuir turbulence parameterizations and key wave effects in a numerical model of the north atlantic and arctic oceans. Ocean Modelling 137, 76–97.

Anderson RG, et al (2011) Biophysical considerations in forestry for climate protection. Front Ecol Environ 3:
1390 174-182. doi: 10.1890/090179

Andreas, E.L., Mahrt, L., Vickers, D., 2015. An improved bulk air–sea surface flux algorithm, including spray-

mediated transfer. Quarterly Journal of the Royal Meteorological Society 141, 642–654.

Argles, A. P. K., Moore, J. R., Huntingford, C., Wiltshire, A. J., Harper, A. B., Jones, C. D., and Cox, P. M. 2020. Robust Ecosystem Demography (RED version 1.0): a parsimonious approach to modelling vegetation dynamics in Earth system models, Geosci. Model Dev., 13, 4067–4089, https://doi.org/10.5194/gmd-13-4067-2020.

Arheimer, B., J. Dahné, and C. Donnelly. 2012. Climate change impact on riverine nutrient load and land-based remedial measures of the Baltic Sea Action Plan. *Ambio* 41: 600–612. https://doi.org/10.1007/s13280-012-0323-0

Axell, L.B., 2002. Wind-driven internal waves and langmuir circulations in a numerical ocean model of the southern baltic sea. Journal of Geophysical Research: Oceans 107, 25–1.

Babanin, A.V., Haus, B.K., 2009. On the existence of water turbulence induced by nonbreaking surface waves. Journal of Physical Oceanography 39, 2675–2679.

Balmaseda, M.A.; Mogensen, K.; Weaver, A.T. (2013): Evaluation of the ECMWF ocean reanalysis system ORAS4.Q J Roy Meteor Soc,139, 1132–1161. doi:10.1002/qj.2063.

Bartosova A, Capell R, Olesen JE, Jabloun M, Refsgaard JC, Donnelly C, Hyytiäinen K, Pihlainen S, Zandersen M, and Arheimer B. (2019). Future socioeconomic conditions may have larger impact on nutrient loads to the Baltic Sea than climate change. Ambio 48: 1325; https://doi.org/10.1007/s13280-019-01243-5

Bauer, T. P., Klingbeil, K., Holtermann, P., Heinold, B., Radtke, H., and Knoth, O.: ICONGETM v1.0 – Flexible two-way coupling via exchange grids between the unstructured-grid atmospheric model ICON and the structured-grid coastal ocean model GETM, Geosci. Model Dev. Discuss. [preprint], https://doi.org/10.5194/gmd-2020-269, in review, 2020.

Beck, H., Zimmermann, N., McVicar, T. et al. Present and future Köppen-Geiger climate classification maps at 1-km resolution. Sci Data 5, 180214 (2018). https://doi.org/10.1038/sdata.2018.214

Belcher, S.E., Grant, A.L., Hanley, K.E., Fox-Kemper, B., Van Roekel, L., Sullivan, P.P., Large, W.G., Brown, A., Hines, A., Calvert, D., et al., 2012. A global perspective on langmuir turbulence in the ocean surface boundary layer. Geophysical Research Letters 39.

Belušić D, et al (2019). Afforestation reduces cyclone intensity and precipitation extremes over Europé. Environ. Res. Lett., 14 074009

Best, M. J., Pryor, M., Clark, D. B., Rooney, G. G., Essery, R. L. H., Ménard, C. B., et al. (2011). The Joint UK Land Environment Simulator (JULES), model description - Part 1: Energy and water fluxes. Geosci. Model Dev. 4, 677–699. doi: 10.5194/gmd-4-677-2011

Bøssing Christensen, O., Kjellström, E., Zorita, E. (2015): Projected change – Atmosphere, second Assessment of Climate Change for the Baltic Sea Basin, Part of the series Regional Climate Studies pp 243-252, DOI:10.1007/978-3-319-16006-1_11

Bøssing Christensen, O., Kjellström, E., Dieterich, C., Gröger, M., Meier, H.E.M., (2021), New Research on Climate Change Projections for the Baltic Sea Region until 2100, ESD Discussions.

Boé, J., Somot, S., Corre, L. et al. Large discrepancies in summer climate change over Europe as projected by global and regional climate models: causes and consequences. Clim Dyn 54, 2981–3002 (2020). https://doi.org/10.1007/s00382-020-05153-1

Bonan GB (2008) Forests and climate change: Forcings, feedbacks, and the climate benefits of forests. Science 320: 1444-1449. doi: 10.1126/science.1155121

1445 Bouwman, A. F., Bierkens, M. F. P., Griffioen, J., Hefting, M. M., Middelburg, J. J., Middelkoop, H., et al. (2013). Nutrient dynamics, transfer and retention along the aquatic continuum from land to ocean: towards integration of ecological and biogeochemical models. Biogeosciences 10, 1–22. doi: 10.5194/bg-10-1-2013

Bremicker, M. (2000). Das Wasserhaushaltsmodell LARSIM - Modellgrundlagen und Anwendungsbeispiele.
1450 Freiburger Schriften zur Hydrologie 11 (Freiburg i. Br.: Univ. Freiburg i. Br.)

Cabos, W., de la Vara, A., Álvarez-García, F.J. et al. Impact of ocean-atmosphere coupling on regional climate: the Iberian Peninsula case. Clim Dyn 54, 4441–4467 (2020). https://doi.org/10.1007/s00382-020-05238-x.

1455 Champeaux, J. L., V. Masson, and F. Chauvin, 2005: ECOCLIMAP: A global database of land surface parameters at 1 km resolution. Meteor. Appl., 12, 29–32, https://doi.org/10.1017/S1350482705001519.

Chen, J., Brissette, F. P., Chaumont, D., and Braun, M. (2013), Finding appropriate bias correction methods in downscaling precipitation for hydrologic impact studies over North America, Water Resour. Res., 49, 4187–
1460 4205, doi:10.1002/wrcr.20331

Claussen M. (2001) Earth System Models. In: Ehlers E., Krafft T. (eds) Understanding the Earth System. Springer, Berlin, Heidelberg

1465 Cornes, R., G. van der Schrier, E.J.M. van den Besselaar, and P.D. Jones. (2018): An Ensemble Version of the E-OBS Temperature and Precipitation Datasets, J. Geophys. Res. Atmos., 123. doi:10.1029/2017JD028200.

Craig, A., Valcke, S., and Coquart, L.: Development and performance of a new version of the OASIS coupler, OASIS3-MCT_3.0, Geosci. Model Dev., 10, 3297–3308, https://doi.org/10.5194/gmd-10-3297-2017, 2017
1470
Craig, P.D., Banner, M.L., 1994. Modeling wave-enhanced turbulence in the ocean surface layer. Journal of Physical Oceanography 24, 2546–2559.

D'Asaro, E.A., 2014. Turbulence in the upper-ocean mixed layer. Annual review of marine science 6, 101–115.
1475
Daewel, U. and Schrum, C. (2017). Low-frequency variability in North Sea and Baltic Sea identified through simulations with the 3-D coupled physical–biogeochemical model ECOSMO. *Earth Syst. Dyn.* 8, 801. doi: 10.5194/esd-8-801-2017

1480 Davies, A.M., Lawrence, J., 1995. Modeling the effect of wave–current interaction on the three-dimensional wind-driven circulation of the eastern irish sea. Journal of Physical Oceanography 25, 29–45.

Dell'Aquila, A., Calmanti, S., Ruti, P., Struglia, M., Pisacane, G., Carillo, A., et al. (2012). Effects of seasonal cycle fluctuations in an a1b scenario over the euro-mediterranean region. *Climate Research* 52, 135–157. doi:
1485 10.3354/cr01037

Dieterich, C., Wang, S., Schimanke, S., Gröger, M., Klein, B., Hordoir, R., Samuelsson, P., Liu, Y., Axell, L., Höglund, A., Meier, H.E.M. (2019a): Surface heat budget over the North Sea in climate change simulations. Atmosphere, 10, 272. doi:10.3390/atmos10050272.
1490
Dieterich, C. and Gröger, M. and Arneborg, L. and Andersson, H. C., 2019b. Extreme sea levels in the Baltic Sea under climate change scenarios -- Part 1: Model validation and sensitivity, Ocean Sci, 15, 6, 1399-1418,

10.5194/os-15-1399-2019

1495 Doescher R, Willen U, Jones C, Rutgersson A, Meier M, Hansson U, et al. (2002)The development of the regional coupled ocean-atmosphere model RCAO. Boreal environment research,7(3), 183–92

Döscher, R., and H.E.M. Meier, 2004: Simulated sea surface temperature and heat fluxes in different climates of the Baltic Sea. Ambio, 33, 242-248

1500

Donnelly, C., Andersson, J. C. M., and Arheimer, B. (2016). Using flow signatures and catchment similarities to evaluate the e-hype multi-basin model across europe. *Hydrol. Sci. J.* 61, 255–273. doi: 10.1080/02626667.2015.1027710

1505 ECMWF, 2017. IFS Documentation CY43r1, Part VII: ECMWF Wave Model. ECMWF Model Documentation. European Centre for Medium-Range Weather Forecasts.

Elizalde, A. (2011). The water cycle in the Mediterranean region and the impacts of climate change. *Phd thesis. Berichte zur Erdsystemforschung* 103, MPI for Meteorology, Hamburg, Germany, doi:10.17617/2.1216556

1510

Ellison D, et al (2017) Trees, forests and water: Cool insights for a hot world. Glob Environ Change 43: 51-61. doi: 10.1016/j.gloenvcha.2017.01.002

Eyring V., Bony S., Meehl G. A., Senior C. A., Stevens B., Stouffer R. J. and Taylor K. E. 2016. Overview of the Coupled Model Intercomparison Project Phase 6 (CMIP6) experimental design and organization. Geosci.
1515 Model Dev., 9, 1937–1958, https://doi.org/10.5194/gmd-9-1937-2016

Fang, Y., Zhang, Y., Tang, J., & Ren, X. (2009): A regional air-sea coupled model and its application over East Asia in the summer of 2000. Advances in Atmospheric Sciences, 27(3).

Fichefet T. and M. A. Morales Maqueda, 1997: Sensitivity of a global sea ice model to the treatment of ice
1520 thermodynamics and dynamics. Journal of Geophysical Research, 102:12,609–12,646

Fiedler, S., Stevens, B., Gidden, M., Smith, S. J., Riahi, K., and van Vuuren, D. (2019), First forcing estimates from the future CMIP6 scenarios of anthropogenic aerosol optical properties and an associated Twomey effect, Geosci. Model Dev., 12, 989–1007, https://doi.org/10.5194/gmd-12-989-2019, 2019

Fiorino, M., 2004, A multi-decadal daily sea-surface temperature and sea-ice con- centration data set for the
1525 ERA-40 reanalysis'. ECMWF ERA-40 Project Report Series, No. 12. European Centre for Medium-Range Weather Forecasts, Shinfield, Reading, UK (available from www.ecmwf.int/publications)

Fischer, E., Schär, C. Consistent geographical patterns of changes in high-impact European heatwaves. Nature Geosci 3, 398–403 (2010). https://doi.org/10.1038/ngeo866

1530

Fisher, R. A., Muszala, S., Verteinstein, M., Lawrence, P., Xu, C., McDowell, N. G., Knox, R. G., Koven, C., Holm, J., Rogers, B. M., Spessa, A., Lawrence, D., and Bonan, G. 2015 Taking off the training wheels: the properties of a dynamic vegetation model without climate envelopes, CLM4.5(ED), Geosci. Model Dev., 8, 3593–3619, https://doi.org/10.5194/gmd-8-3593-2015.

1535

Fisher, R. A., Koven, C. D., Anderegg, W. R. L., Christoffersen, B. O., Dietze, M. C., Farrior, C. E., Holm, J. A., Hurtt, G. C., Knox, R. G., Lawrence, P. J., Lichstein, J. W., Longo, M., Matheny, A. M., Medvigy, D., Muller-Landau, H. C., Powell, T. L., Serbin, S. P., Sato, H., Shuman, J. K., Smith, B., Trugman, A. T., Viskari, T., Verbeeck, H., Weng, E., Xu, C., Xu, X., Zhang, T., and Moorcroft, P. R.. 2018. Vegetation demographics in
1540 Earth System Models: A review of progress and priorities, Glob. Change Biol., 24, 35–54, https://doi.org/10.1111/gcb.13910, 2018

Flato, G., Marotzke, J., Abiodun, B., Braconnot, P., Chou, S., Collins, W., et al. (2013). Evaluation of climate models. In Climate Change 2013: The Physical Science Basis. Contribution of Working Group I to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change, eds. T. Stocker, D. Qin, G.-K.

1545   Plattner, M. Tignor, S. Allen, J. Boschung, A. Nauels, Y. Xia, V. Bex, and P. Midgley, Cambridge University Press, Cambridge, United Kingdom and New York, NY, USA, 741–866

Flato, G. M. and W. D. Hibler, 1992: Modeling pack ice as a cavitating fluid. J. Phys.Oceanogr.,22, 626–651

Flynn, C. M. and Mauritsen, T., 2020. On the Climate Sensitivity and Historical Warming Evolution in Recent Coupled Model Ensembles, Atmos. Chem. Phys. Discuss., https://doi.org/10.5194/acp-2019-1175, in review.

1550   Gálos, B., A. Hänsler, G. Kindermann, D. Rechid, K. Sieck, and D. Jacob, 2012: The role of forests in mitigating climate change—A case study for Europe. Acta Silv. Lign. Hung., 8, 87–102, https://doi.org/10.2478/v10303-012-0007-2.

Gao Y, Markkanen T, Backman L, Henttonen HM, Pietikäinen J-P, Mäkelä HM, Laaksonen A (2014) Biogeophysical impacts of peatland forestation on regional climate changes in Finland. Biogeosciences 11:
1555   2751-2767. doi: 10.5194/bg-11-7251-2014

Geyer, B., Ludwig, T. & von Storch, H. Limits of reproducibility and hydrodynamic noise in atmospheric regional modelling. *Commun Earth Environ* **2,** 17 (2021). https://doi.org/10.1038/s43247-020-00085-4

Gibson, R., Kallberg, P. und Uppala, S. (1996): The ECMWF Re-Analysis (ERA) project. ECMWF, Newsletter, 73, 7-17.

1560   Giorgi, F., and Bi, X. (2000), A study of internal variability of a regional climate model, *J. Geophys. Res.*, 105(D24), 29503– 29521, doi:10.1029/2000JD900269.

Giorgi, F. (2019). Thirty years of regional climate modeling: Where are we and where are we going next? Journal of Geophysical Research: Atmospheres, 124, 5696– 5723. https://doi.org/10.1029/2018JD030094

1565   Giorgi, F., Gao, X.J., (2018), Regional earth system modeling: review and future direction, Atmospheric and Oceanic Science Letters, 11 (2), DOI: 10.1080/16742834.2018.1452520

Gröger, M., Maier-Reimer, E., Mikolajewicz, U., Moll, A., and Sein, D. (2013).: NW European shelf under climate warming: implications for open ocean – shelf exchange, primary production, and carbon absorption, Biogeosciences, 10, 3767–3792, https://doi.org/10.5194/bg-10-3767-2013.

1570   Gröger, M., Dieterich, C., Meier, H.E.M., Schimanke, S., (2015) Thermal air–sea coupling in hindcast simulations for the North Sea and Baltic Sea on the NW European shelf, Tellus A: Dynamic Meteorology and Oceanography, 67:1, DOI: 10.3402/tellusa.v67.26911

Gröger, M., Arneborg, L., Dieterich, C., Höglund, A., and Meier, H.E.M. (2019), Summer hydrographic changes in the Baltic Sea, Kattegat and Skagerrak projected in an ensemble of climate scenarios downscaled
1575   with a coupled regional ocean–sea ice–atmosphere model. *Clim Dyn* **53,** 5945–5966 doi:10.1007/s00382-019-04908-9

Gröger, M., Dieterich, C. & Meier, H.E.M. (2021), Is interactive air sea coupling relevant for simulating the future climate of Europe?. *Clim Dyn* **56,** 491–514. https://doi.org/10.1007/s00382-020-05489-8

Guimberteau, M., Drapeau, G., Ronchail, J., Sultan, B., Polcher, J., Martinez, J.-M., et al. (2012). Discharge
1580   simulation in the sub-basins of the amazon using ORCHIDEE forced by new datasets. Hydrol. Earth Syst. Sci. 16, 911–935. doi: 10.5194/hess-16-911-2012

Gustafsson, N., Nyberg, L., & Omstedt, A. (1998). Coupling of a High-Resolution Atmospheric Model and an Ocean Model for the Baltic Sea, Monthly Weather Review, 126(11), 2822-2846.

Gustafsson, B. G., F. Schenk, T. Blenckner, K. Eilola, H. E. M. Meier, B. Müller-Karulis, T. Neumann, T. Ruoho-Airola, O.P. Savchuk, and E. Zorita, 2012: Reconstructing the development of Baltic Sea eutrophication 1850-2006. AMBIO, 41 (6), 534-548, doi:10.1007/s13280-012-0317-y

Haapala J., H.E.M. Meier, Rinne J., 2001: Numerical Investigations of Future Ice Conditions in the Baltic Sea, AMBIO, 30(4), 237-2004.

Haapala, J., Lönnroth, N., and Stössel, A. (2005), A numerical study of open water formation in sea ice, J. Geophys. Res., 110, C09011, doi:10.1029/2003JC002200.

Hagemann, S. and Dümenil, L. (1998). A parametrization of the lateral waterflow for the global scale. Climate Dyn. 14, 17–31. doi: 10.1007/s003820050205

Hagemann, S.; Stacke, T. and Ho-Hagemann, H. T. M. (2020). High resolution discharge simulations over Europe and the Baltic Sea catchment. Front. Earth Sci. 8, doi: 10.3389/feart.2020.00012

Hall, A. (2014). Projecting regional change. *Science*, 346(6216), 1461 – 1462. DOI: doi.org/10.1126/science.aaa0629

Hanke, M., Redler, R., Holfeld, T., and Yastremsky, M.: YAC 1.2.0: new aspects for coupling software in Earth system modelling, Geosci. Model Dev., 9, 2755–2769, https://doi.org/10.5194/gmd-9-2755-2016, 2016

Hantson, S., Knorr, W., Schurgers, G., Pugh, TAM, and Arneth, A. (2017) Atmos. Env., 155, pp. 35-45. DOI:10.1016/j.atmosenv.2017.02.010

Haverd, V. Benjamin Smith, Garry D. Cook, Peter R. Briggs, Lars Nieradzik, Stephen H. Roxburgh, Adam Liedloff, Carl P. Meyer, Josep G. Canadell. 2013. A stand-alone tree demography and landscape structure module for Earth system models. Geophysical Reserach letters, Volume 40 (19), Pages 5234-5239

Haverd, V., Smith, B., Nieradzik, L. P., and Briggs, P. R. 2014. A stand-alone tree demography and landscape structure module for Earth system models: integration with inventory data from temperate and boreal forests, Biogeosciences, 11, 4039–4055, https://doi.org/10.5194/bg-11-4039-2014

Haverd, V., Smith, B., Nieradzik, L., Briggs, P. R., Woodgate, W., Trudinger, C. M., Canadell, J. G., and Cuntz, M.. 2018. A new version of the CABLE land surface model (Subversion revision r4601) incorporating land use and land cover change, woody vegetation demography, and a novel optimisation-based approach to plant coordination of photosynthesis, Geosci. Model Dev., 11, 2995–3026, https://doi.org/10.5194/gmd-11-2995-2018.

Hay, L.E., Wilby, R.L. and Leavesley, G.H. (2000), A Comparison of delta change and downscaled GCM sceanrios for three mountainous basins in the United States. JAWRA Journal of the American Water Resources Association, 36: 387-397. doi:10.1111/j.1752-1688.2000.tb04276.x

Heinze, C., Eyring, V., Friedlingstein, P., Jones, C., Balkanski, Y., Collins, W., Fichefet, T., Gao, S., Hall, A., Ivanova, D., Knorr, W., Knutti, R., Löw, A., Ponater, M., Schultz, M. G., Schulz, M., Siebesma, P., Teixeira, J., Tselioudis, G., & Vancoppenolle, M. (2019). Climate feedbacks in the Earth system and prospects for their evaluation. Earth System Dynamics, 10, 379– 452. https://doi.org/10.5194/esd-10-379-2019

Heinze, R. et al. (2017): Large-eddy simulations over Germany using ICON: a comprehensive evaluation. Q. J. R. Meteorol. Soc., 143(702), 69–100. https://doi.org/10.1002/qj.2947.

Hersbach, H. and Dee, D. (2016): ERA5 reanalysis is in production. ECMWF Newsletter 2016, 147.

Hertig, E. and Jacobeit, J. (2014), Variability of weather regimes in the North Atlantic-European area: past and future. Atmos. Sci. Lett., 15: 314-320. doi:10.1002/asl2.505

Hibler, W. D., 1979: A dynamic thermodynamic sea ice model. J. Phys. Oceanogr.,9, 815–846.

Hibler, W. D., 1980: Modeling a variable thickness ice cover. Mon. Wea. Rev.,108, 1943–1973.

Hickler T, et al (2012) Projecting the future distribution of European potential natural vegetation zones with a generalized, tree species-based dynamic vegetation model. Global Ecol Biogeogr 21: 50-63. doi: 10.1111/j.1466-8238.2010.00613.x

Ho-Hagemann, H.T.M., Hagemann, S., Rockel, B. (2015): On the role of soil moisture in the generation of heavy rainfall during the Oder flood event in July 1997. Tellus A, 67, 28661. doi:10.3402/tellusa.v67.28661.

Ho-Hagemann, H.T.M., Gröger, M., Rockel, B., Zahn, M., Geyer, B., Meier, H.E.M. (2017): Effects of air-sea coupling over the North Sea and the Baltic Sea on simulated summer precipitation over Central Europe. Climate Dyn., pp. 1–26. doi:10.1007/s00382-017-3546-8.

Ho-Hagemann, H.T.M., Hagemann, S., Grayek, S., Petrik, R., Rockel, B., Staneva, J., Feser, F., Schrum, C. (2020): Internal model variability in the regional coupled system model GCOAST-AHOI, Atmosphere, 11, 227; doi:10.3390/atmos11030227; pdf: https://www.mdpi.com/2073-4433/11/3/227/pdf.

Ho-Hagemann, H.T.M. and B. Rockel (2018): Einfluß von Atmosphäre-Ozean Wechselwirkungen auf Starkniederschläge über Europa. In: Lozán, J. L., S.-W. Breckle, H. Graßl, D. Kasang & R. Weisse (Hrsg.). Warnsignal Klima: Extremereignisse. pp. 161-168. Online: www.klima-warnsignale.uni-hamburg.de. doi:10.2312/warnsignal.klima.extremereignisse.23

Holt, J., C. Schrum, H. Cannaby, U. Daewel, J.I. Allen, Y. Artioli, L. Bopp, M. Butenschon, B.A. Fach, J. Harle, D. Pushpadas, B. Salihoglu, S. Wakelin, Potential impacts of climate change on the primary production of regional seas: a comparative analysis of five European seas, Prog. Oceanogr., 140 (2016), pp. 91-115, 10.1016/j.pocean.2015.11.004

Hordoir, R. and Meier, H. E. M. (2010). Freshwater fluxes in the Baltic Sea: A model study. J. Geophys. Res. 115, C08028. doi: 10.1029/2009jc005604

Hordoir, R., Polcher, J., Brun-Cottan, J.-C., and Madec, G. (2008). Towards a parametrization of river discharges into ocean general circulation models: a closure through energy conservation. *Climate Dyn.* 31, 891–908. doi: 10.1007/s00382-008-0416-4

Hordoir, R., Axell, L., Höglund, A., Dieterich, C., Fransner, F., Gröger, M., Liu, Y., Pemberton, P., Schimanke, S., Andersson, H., Ljungemyr, P., Nygren, P., Falahat, S., Nord, A., Jönsson, A., Lake, I., Döös, K., Hieronymus, M., Dietze, H., Löptien, U., Kuznetsov, I., Westerlund, A., Tuomi, L., and Haapala, J. (2019): Nemo-Nordic 1.0: a NEMO-based ocean model for the Baltic and North seas – research and operational applications, Geosci. Model Dev., 12, 363–386, https://doi.org/10.5194/gmd-12-363-2019.

Hunke, E. C. and J. K. Dukowicz, 1997: An elastic-viscous-plastic model for sea ice dynamics. J. Phys. Oceanogr.,27, 1849–1867

Hurrell, J.W. Decadal trends in the North Atlantic Oscillation: Regional temperatures and precipitation. Science 1995, 269, 676–679

Hurtt, G. C., Chini, L., Sahajpal, R., Frolking, S., Bodirsky, B. L., Calvin, K., Doelman, J. C., Fisk, J., Fujimori,

1670 S., Goldewijk, K. K., Hasegawa, T., Havlik, P., Heinimann, A., Humpenöder, F., Jungclaus, J., Kaplan, J., Kennedy, J., Kristzin, T., Lawrence, D., Lawrence, P., Ma, L., Mertz, O., Pongratz, J., Popp, A., Poulter, B., Riahi, K., Shevliakova, E., Stehfest, E., Thornton, P., Tubiello, F. N., van Vuuren, D. P., and Zhang, X.: Harmonization of Global Land-Use Change and Management for the Period 850–2100 (LUH2) for CMIP6, Geosci. Model Dev., 13, 5425-5464.,doi: 10.5194/gmd-13-5425-2020.

1675 IPCC, 2013: Climate Change 2013: The Physical Science Basis. Contribution of Working Group I to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change [Stocker, T.F., D. Qin, G.-K. Plattner, M. Tignor, S.K. Allen, J. Boschung, A. Nauels, Y. Xia, V. Bex and P.M. Midgley (eds.)]. Cambridge University Press, Cambridge, United Kingdom and New York, NY, USA, 1535 pp

1680 IPCC, 2019: Summary for Policymakers. In: Climate Change and Land: an IPCC special report on climate change, desertification, land degradation, sustainable land management, food security, and greenhouse gas fluxes in terrestrial ecosystems [P.R. Shukla, J. Skea, E. Calvo Buendia, V. Masson-Delmotte, H.- O. Pörtner, D. C. Roberts, P. Zhai, R. Slade, S. Connors, R. van Diemen, M. Ferrat, E. Haughey, S. Luz, S. Neogi, M. Pathak, J. Petzold, J. Portugal Pereira, P. Vyas, E. Huntley, K. Kissick, M. Belkacemi, J. Malley, (eds.)]. In 1685 press

Jacob (2001) A note to the simulation of the annual and inter-annual variability of the water budget over the Baltic Sea drainage basin, *Meteorol. Atmos. Phys.* 77, 61-73, https://doi.org/10.1007/s007030170017

1690 Jacob, D., Petersen, J., Eggert, B. *et al.* (2014), EURO-CORDEX: new high-resolution climate change projections for European impact research. *Reg Environ Change* **14,** 563–578. https://doi.org/10.1007/s10113-013-0499-2

Jacob, D., Teichmann, C., Sobolowski, S. et al. (2020), Regional climate downscaling over Europe: perspectives 1695 from the EURO-CORDEX community. Reg Environ Change 20, https://doi.org/10.1007/s10113-020-01606-9

Jakacki J., S. Meler, (2018): An evaluation and implementation of the regional coupled ice-ocean model of the Baltic Sea, Ocean Dynamics https://doi.org/10.1007/s10236-018-1219-8

Jakacki J., Przyborska A., Nowicki A., Wichorowski M., Przyborski M., Białoskórski M., Sochacki C., R. 1700 Tylman, (2017): eBalticGrid - an interactive platform for the visualisation of results from a high-resolution operational Baltic Sea model. Meteorol. Hydrol. Water Manage. vol. 5; (2):13-20

James, P.M. (2006): An assessment of European synoptic variability in Hadley Centre Global Environmental models based on an objective classification of weather regimes, Clim Dyn 27:215–231. doi:10.1007/s00382-1705 006-0133-9.

James, P.M. (2007): An objective classification method for Hess and Brezowsky Grosswetterlagen over Europe. Theoretical and Applied Climatology 88:17-42.

1710 Janecki M., A. Nowicki, A. Kańska, M. Golenko, L. Dzierzbicka-Głowacka, 2018: Numerical simulations of sea-ice conditions in the Baltic Sea for 2010–2016 winters using the 3D CEMBS model, Polish Maritime Research 25(3), 35-43, https://doi.org/10.2478/pomr-2018-0094

Janssen, P.A., Saetra, O., Wettre, C., Hersbach, H., Bidlot, J., 2004. Impact of the sea state on the atmosphere 1715 and ocean, in: Annales hydro-graphiques, Service hydrographique et océanographique de la marine. pp. 3–1.

Janssen, P.A., Viterbo, P., 1996. Ocean waves and the atmospheric climate. Journal of Climate 9, 1269–1287.

Jeworrek, J., Wu, L., Dieterich, C., Rutgersson, A., 2017. Characteristics of convective snow bands along the 1720 swedish east coast. Earth System Dynamics 8, 163–175.

Jones, C. D., Arora, V., Friedlingstein, P., Bopp, L., Brovkin, V., Dunne, J., Graven, H., Hoffman, F., Ilyina, T., John, J. G., Jung, M., Kawamiya, M., Koven, C., Pongratz, J., Raddatz, T., Randerson, J. T., and Zaehle, S.: C4MIP – The Coupled Climate–Carbon Cycle Model Intercomparison Project: experimental protocol for CMIP6, Geosci. Model Dev., 9, 2853–2880, https://doi.org/10.5194/gmd-9-2853-2016, 2016

Jungclaus et al., 2006 Hundecha, Y., B. Arheimer, C. Donnelly, and I. Pechlivanidis (2016). A regional parameter estimation scheme for a pan-European multi-basin model. Journal of Hydrology: Regional Studies 6: 90–111. https://doi.org/10.1016/j.ejrh.2016.04.002

Jungclaus, J. H., Keenlyside, N., Botzet, M., Haak, H., Luo, J.-J., Latif, M., et al. (2006). Ocean circulation and tropical variability in the coupled model ECHAM5/MPI-OM. J. Climate 19, 3952

Kalnay, E., Kanamitsu, M., Kistler, R., Collins,W., Deaven, D., Gandin, L., Iredell, M., Saha, S., White, G., Woollen, J., Zhu, Y., Chelliah, M., Ebisuzaki, W., Higgins, W., Janowiak, J., Mo, K. C., Ropelewski, C., Wang, J., Leetmaa, A., Reynolds, R., Jenne, R. and Joseph, D. (1996): The NCEP/NCAR 40-Year Reanalysis Project. Bulletin of the American Meteorological Society.

Kelemen, F.D., Primo, C., Feldmann, H., Ahrens, B. (2019), Added Value of Atmosphere-Ocean Coupling in a Century-Long Regional Climate Simulation, Atmosphere, *10*(9), 537; https://doi.org/10.3390/atmos10090537

Kerr, R., 2013, Forecasting Regional Climate Change Flunks Its First Test, Science 08 Feb 2013: Vol. 339, Issue 6120, pp. 638, DOI: 10.1126/science.339.6120.638

Kjellström E, Döscher R, Meier HEM (2005) Atmospheric response to different sea surface temperatures in the Baltic Sea: coupled versus uncoupled regional climate model experiments. Hydrol Res 36(4–5):397–409. https://doi.org/10.2166/nh.2005.0030

Kjellström E, Bärring L, Nikulin G, Nilsson C, Persson G and Strandberg G 2016 Production and use of regional climate model projections—a Swedish perspective on building climate services Clim. Serv. 2-3 15–29

Kjellström E, Nikulin G, Strandberg G, Christensen OB, Jacob D, Keuler K, Lenderink G, van Meijgaard E, Schär C, Somot S, Sørland SL, Teichmann C, Vautard R (2018) European climate change at global mean temperature increases of 1.5 and 2 °C above pre-industrial conditions as simulated by the EURO-CORDEX regional climate models. Earth Syst Dyn 9:459–478. https://doi.org/10.5194/esd-9-459-2018

Knudsen, M. (1900). Ein hydrographischer lehrsatz. Annalen der Hydrographie und Maritimen Meteorologie, 28 (7), 316-320.

Koca D, Smith, B, Sykes MT (2006) Modelling regional climate change effects on potential natural ecosystems in Sweden. Clim Change 78: 381-406. doi: 10.1007/s10584-005-9030-1

Kotlarski, S., Keuler, K., Christensen, O. B., Colette, A., Déqué, M., Gobiet, A., et al. (2014). Regional climate modeling on European scales: a joint standard evaluation of the EURO-CORDEX RCM ensemble. Geosci. Model Dev. 7, 1297–1333. doi: 10.5194/gmd-7-1297-2014

Kottek, M., J. Grieser, C. Beck, B. Rudolf, and F. Rubel, 2006: World Map of the Köppen-Geiger climate classification updated. Meteorol. Z., 15, 259-263. DOI: 10.1127/0941-2948/2006/0130

Koven, C. D., R. G. Knox, R. A. Fisher, J. Q. Chambers, B. O. Christoffersen, S. J. Davies, M. Detto, M. C. Dietze, B. Faybishenko, J. Holm, M. Huang, M. Kovenock, L. M. Kueppers, G. Lemieux, E. Massoud, N. G. McDowell, H. C. Muller-Landau, J. F. Needham, R. J. Norby, T. Powell, A. Rogers, S. P. Serbin, J. K. Shuman, A. L. S. Swann, C. Varadharajan, A. P. Walker, S. J. Wright and C. Xu. 2020. Benchmarking and parameter sensitivity of physiological and vegetation dynamics using the Functionally Assembled Terrestrial Ecosystem

1775 Simulator (FATES) at Barro Colorado Island, Panama. Biogeosciences 17(11): 3017-3044 DOI: 10.5194/bg-17-3017-2020.

Köppen, W., (1923): Die Klimate der Erde, Walter de Gruyter, Berlin. Available at http://koeppen-geiger.vu-wien.ac.at/pdf/Koppen_1936.pdf

1780 Kudryavtsev, V.N., Makin, V.K., 2011. Impact of ocean spray on the dynamics of the marine atmospheric boundary layer. Boundary-layer meteorology 140, 383–410.

Kuliński, K., Rehder, G., Asmala, E., Bartosova, A., Carstensen, J., Gustafsson, B., Hall, P.O.J., Humborg, C., Jilbert, T., Jürgens, K., Meier, H.E.M., Müller-Karulis, B., Naumann, M., Olesen, J.E., Savchuk,O., Schramm, 1785 A., Slomp, C.P., Sofiev, M., Sobek,A., Szymczycha, B., Undeman, E. Baltic Earth Assessment Report on the biogeochemistry of the Baltic Sea, ESD Discussions

Kulmala, M, Nieminen, T, Nikandrova, A, Lehtipalo, K, Manninen, HE, Kajos, MK, Kolari, P, Lauri, A, Petaja, T, Krejci, R, Hansson, H-C, Swietlicki, E, Lindroth, A, Christensen, T, Arneth, A, Hari, P, Back, J, Vesala, T & 1790 Kerminen, V-M (2014), 'CO2-induced terrestrial climate feedback mechanism: From carbon sink to aerosol source and back', Boreal Environment Research, vol. 19, pp. 122-131.

Kumkar, Y., R. Astrup, F. Stordal and R. M. Bright. 2020. Quantifying Regional Surface Energy Responses to Forest Structural Change in Nordic Fennoscandia. Journal of Geophysical Research-Atmospheres 125(15): 17 DOI: 10.1029/2019jd032092.

1795

Lagergren F, Jönsson AM (2017) Ecosystem model analysis of multi-use forestry in a changing climate. Ecosyst Serv 26: 209-224. doi: 10.1016/j.ecoser.2017.06.007

Larsen, M. A. D., Refsgaard, J. C., Drews, M., Butts, M. B., Jensen, K. H., Christensen, J. H., et al. (2014). Results from a full coupling of the HIRHAM regional climate model and the MIKE SHE hydrological model 1800 for a danish catchment. Hydrol. Earth Syst. Sci. 18, 4733–4749. doi: 10.5194/hess-18-4733-2014

Larsén, X.G., Du, J., Bolaños, R., Imberger, M., Kelly, M.C., Badger, M., Larsen, S., 2019. Estimation of offshore extreme wind from wind-wave coupled modeling. Wind Energy .

1805 Lawrence, D. M., Oleson, K. W., Flanner, M. G., Thornton, P. E., Swenson, S. C., Lawrence, P. J., et al. (2011). Parameterization improvements and functional and structural advances in version 4 of the community land model. *J. Adv. Model. Earth Syst.* 3, M03001. doi: 10.1029/2011MS00045

Lee, J.-W., Hong, S.-Y., Kim, J.-E. E., Yoshimura, K., Ham, S., and Joh, M. (2015). Development and 1810 implementation of river-routing process module in a regional climate model and its evaluation in korean river basins. *J. Geophys. Res. Atmos.* 120, 4613–4629. doi: 10.1002/2014JD022698

Lehmann, A. and Hinrichsen, H.-H. (2000). On the thermohaline variability of the Baltic Sea. *J. Mar. Syst.* 25, 333–357. doi: 10.1016/s0924-7963(00)00026-9
1815

Lehmann, A., Myrberg, K., 2008. Upwelling in the baltic sea review. Journal of Marine Systems 74, S3–S12. McWilliams, J.C., Sullivan, P.P., 2000. Vertical mixing by langmuir circulations. Spill Science & Technology Bulletin 6, 225–237.

1820 Lemmen, C., Hofmeister, R., Klingbeil, K., Nasermoaddeli, M. H., Kerimoglu, O., Burchard, H., Kösters, F., and Wirtz, K. W. 2018: Modular System for Shelves and Coasts (MOSSCO v1.0) – a flexible and multi-component framework for coupled coastal ocean ecosystem modelling, Geosci. Model Dev., 11, 915–935, https://doi.org/10.5194/gmd-11-915-2018

1825   Lengaigne, M., Madec, G., Bopp, L., Menkes, C., Aumont, O., and Cadule, P. (2009), Bio-physical feedbacks in the Arctic Ocean using an Earth system model, Geophys. Res. Lett., 36, L21602, doi:10.1029/2009GL040145

Lemieux J.F., F. Dupont, P. Blaine, F. Roy, G. C. Smith, G. M. Flato, 2016: Improving the simulation of landfast ice by combining tensile strength and a parameterization for grounded ridges. Journal of Geophysical
1830   Research: Oceans. 121 (10): 7354–7368.

Leppäranta, M., and Myrberg, K. (2009). Physical Oceanography of the Baltic Sea. Springer Science & Business Media

1835   Li, L. Z. X. (2006): Atmospheric GCM response to an idealized anomaly of the Mediterranean sea surface temperature. Clim. Dyn., 27:543–552.

Liepert, B.G., and F. Lo (2013) CMIP5 update of 'Inter-model variability and biases of the global water cycle in CMIP3 coupled climate models'. *Environ. Res. Lett.* 8, 029401, doi:10.1088/1748-9326/8/2/029401.

Lind, P. & Kjellström, E. (2009) Water budget in the Baltic Sea drainage basin: Evaluation of simulated fluxes
1840   in a regional climate model. *Boreal Environ. Res.* 14, 56-67

Lindeskog M, et al (2013) Implications of accounting for land use in simulations of ecosystem carbon cycling in Africa. Earth Syst. Dynam. 4: 385-407. doi: 10.5194/esd-4-385-2013

Lorenz and Jacob, 2014Lorenz, P. and Jacob, D. (2014). BALTIMOS — a coupled modelling system for the
1845   Baltic Sea and its drainage basin. *Theor. Appl. Climatol.* 118, 715. doi: 10.1007/s00704-014-1276-y

Luyssaert S, et al (2014) Land management and land-cover change have impacts of similar magnitude on surface temperature. Nat Clim Change 4: 389-393. doi: 10.1038/NCLIMATE2196

Luyssaert S, et al (2018) Trade-offs in using European forests to meet climate objectives. Nature 562: 259-267.
1850   doi: 10.1038/s41586-018-0577-1

Mahmood R, et al (2014) Land cover changes and their biogeophysical effects on climate. Int J Climatol 34: 929-953. doi: 10.1002/joc.3736

Mathis, M., Elizalde, A. & Mikolajewicz, U. (2018), Which complexity of regional climate system models is essential for downscaling anthropogenic climate change in the Northwest European Shelf?. *Clim Dyn* **50,** 2637–
1855   2659. https://doi.org/10.1007/s00382-017-3761-3

Mauser, W. and Bach, H. (2009). PROMET - Large scale distributed hydrological modelling to study the impact of climate change on the water flows of mountain watersheds. *J. Hydrol.* 376, 362–377. doi: 10.1016/j.jhydrol.2009.07.046
1860

May, W., Ganske, A., Leckebusch, G.C., Rockel, B., Tinz, B., Ulbrich, U. (2016): Projected Change— Atmosphere, North Sea Region Climate Change Assessment, Part of the series Regional Climate Studies pp 149-173, DOI: 10.1007/978-3-319-39745-0_5

1865   May. W., P. A. Miller and B. Smith (2020) The importance of land-atmosphere biophysical interactions for regional climate and terrestrial ecosystem change: Improved understanding to inform Swedish national climate action. CEC Synthesis Report No. 5. Centre for Environmental and Climate Research, Lund University, 152

Maykut, G. A., and Untersteiner, N. (1971), Some results from a time-dependent thermodynamic model of sea
1870   ice, J. Geophys. Res., 76(6), 1550– 1575, doi:10.1029/JC076i006p01550

McClean, J. L., Bader, D. C., Bryan, F. O., Maltrud, M. E., & Dennis, J. M. (2011): A prototype two-decade fully-coupled fine-resolution CCSM simulation. Ocean Modelling, 39, 10–30.

1875   Melville, W.K., Veron, F., White, C.J., 2002. The velocity field under breaking waves: coherent structures and turbulence. Journal of Fluid Mechanics 454, 203–233.

Meier, H. E. M., 2002a: Regional ocean climate simulations with a 3D ice-ocean model for the Baltic Sea: 1. Model experiments and results for temperature and salinity, Clim. Dyn., 19, 237 – 253,

1880   Meier, H. E. M., 2002b: Regional ocean climate simulations with a 3D ice-ocean model for the Baltic Sea: 2. Results for sea ice, Clim. Dyn., 19, 255 – 266.

Meier, H. E. M., and R. Döscher, 2002: Simulated water and heat cycles of the Baltic Sea using a 3D coupled atmosphere-ice-ocean model, Boreal Environ. Res., 7, 327 – 334

Markus H.E. M., R. Döscher and A. Halkka, 2004: Simulated Distributions of Baltic Sea-ice in Warming

1885   Climate and Consequences for the Winter Habitat of the Baltic Ringed Seal, Ambio Vol. 33 No. 4–5.

Meier, H.E.M. 2015: Projected change – Marine Physics, Second Assessment of Climate Change for the Baltic Sea Basin, Part of the series Regional Climate Studies pp 243-252, DOI:10.1007/978-3-319-16006-1_13

1890

Meier, H.E.M., Dieterich, C., Eilola, K. Gröger, M., Höglund, A., Radtke, H., Saraiva, S., Wåhlström, I. (2019a), Future projections of record-breaking sea surface temperature and cyanobacteria bloom events in the Baltic Sea. Ambio 48, 1362–1376 . DOI: 10.1007/s13280-019-01235-5.

1895   Meier, H.E.M., and F. Kauker, 2003: Modeling decadal variability of the Baltic Sea: 2. Role of freshwater inflow and large-scale atmospheric circulation for salinity. J. Geophys. Res., 108(C11), 3368, doi:10.1029/2003JC001799

Meier, H.E.M., A. Höglund, R. Döscher, H. Andersson, U. Löptien and E. Kjellström, 2011: Quality assessment

1900   of atmospheric surface fields over the Baltic Sea of an ensemble of regional climate model simulations with respect to ocean dynamics. Oceanologia , 53, 193-227

Meier , H.E.M., Edman, M., Eilola, K., Placke, M., Neumann, T., Andersson, H., Brunnabend, S., Dieterich, C., Frauen, C., Friedland, R., Gröger, M.,Gustafsson, B., Gustafsson, E., Isaev, A., Kniebusch, M., Kuznetsov,I.,

1905   Müller-Karulis, B., Naumann, M., Omstedt, A., Ryabchenko, V., Saraiva, S., and Savchuk, O. (2019b), Assessment of uncertainties in scenario simulations of biogeochemical cycles in the Baltic Sea Front. Mar. Sci., 6:46 DOI:10.3389/fmars.2019.00046.

Meier, H.E.M, Edman,M., Eilola, K.,Placke, M., Neumann, T., Andersson, H., Brunnabend, S.-E., Dieterich, C., Frauen,C., Friedland,R., Gröger, M, Gustafsson, B., Gustafsson, E., Isaev, A., Kniebusch,M., Kuznetsov, I.,

1910   Müller-Karulis, B., Omstedt, A., Ryabchenko, V., Saraiva,S., Savchuk.O.P., (2018) Assessment of eutrophication abatement scenarios for the Baltic Sea by multi-model ensemble simulations, Front. Mar. Sci. - Coastal Ocean Processes, 5, 440, DOI:10.3389/fmars.2018.00440

Meier, H.E.M., R. Hordoir, H.C. Andersson, C. Dieterich, K. Eilola, B.G. Gustafsson, A. Höglund, and S.

1915   Schimanke, (2012): Modeling the combined impact of changing climate and changing nutrient loads on the Baltic sea environment in an ensemble of transient simulations for 1961-2099. _Clim. Dyn. _, 39, 2421-2441, doi: 10.1007/s00382-012-1339-y.

Meier, H.E.M., Börgel, F., Bøssing-Christensen, O., Dieterich, C., Dutheil, C., Edman, M., Gröger, M.,

1920   Kjellström, E., (2021), Baltic Sea scenario simulations - a review, ESD Discussions

Mikolajewicz, U., Sein, D.V., Jacob, D., Konigk, T., Podzun, R., Semmler, T. (2005): Simulating Arctic sea ice variability with a coupled regional atmosphere-ocean-sea ice model. Meteorol. Z. , 14, 793–800.

doi:10.1127/0941-2948/2005/0083.

1925

Miller PA, Giesecke T, Hickler T, Bradshaw RHW, Smith B, Seppä H, Valdes PJ, Sykes MT (2008) Exploring climatic and biotic controls on Holocene vegetation change in Fennoscandia. J Ecol 96: 247-259. doi: 10.1111/j.1365-2745.2007.01342.x

Milly, P. C. D., Malyshev, S. L., Shevliakova, E., Dunne, K. A., Findell, K. L., Gleeson, T., et al. (2014). An
1930   enhanced model of land water and energy for global hydrologic and earth-system studies. *J. Hydrometeorol*. 15, 1739–1761. doi: 10.1175/jhm-d-13-0162.1

Moorcroft, P.R., G.C. Hurtt, and S.W. Pacala. 2001. A method for scaling vegetation dynamics: the ecosystem demography model ED. Ecological monographs 71.4, pp. 557-586.

1935   Nguyen-Quang, T., Polcher, J., Ducharne, A., Arsouze, T., Zhou, X., Schneider, A. and Fita, L. (2018). ORCHIDEE-ROUTING: revising the river routing scheme using a high-resolution hydrological database. *Geosci. Model Dev.* 11, 4965-4985, doi: 10.5194/gmd-11-4965-2018

NRC: Understanding Climate Change Feedbacks, National Research Council (NRC), Panel on Climate Change
1940   Feedbacks, Cli-mate Research Committee, 2003, Ebook available,
https://www.nap.edu/catalog/10850/understanding-climate-change-feedbacks

Nilsson, E.O., Rutgersson, A., Smedman, A.S., Sullivan, P.P., 2012. Convective boundary-layer structure in the presence of wind-following swell. Quarterly Journal of the Royal Meteorological Society 138, 1476–1489.
1945   Polton, J.A., Lewis, D.M., Belcher, S.E., 2005. The role of wave-induced coriolis–stokes forcing on the wind-driven mixed layer. Journal of Physical Oceanography 35, 444–457.

Oki, T. and Sud, Y. C. (1998). Design of total runoff integrating pathways (TRIP) - A global river channel network. *Earth Interact* 2, 1–37. doi: 10.1175/1087-3562(1998)002<0001:dotrip>2.3.co;2

1950

Olin S, et al (2015a) Modelling the response of yields and tissue C : N to changes in atmospheric CO_2 and N management in the main wheat regions of western Europe. Biogeosciences 12: 2489-2515. doi: 10.5194/bg-12-2489-2015

Olin S, et al (2015b) Soil carbon management in large-scale Earth system modelling: implications for crop
1955   yields and nitrogen leaching. Earth Syst. Dynam. 6: 745-768. doi: 10.5194/esd-6-745-2015

Österblom et al., 2007Österblom, H., Hansson, S., Larsson, U., Hjerne, O., Wulff, F., Elmgren, R., et al. (2007). Human-induced trophic cascades and ecological regime shifts in the Baltic Sea. *Ecosystems* 10, 877–889. doi: 10.1007/s10021-007-9069-0

1960   Pemberton P., U. Löptien, R. Hordoir, A. Höglund, S. Schimanke, L. Axell, J. Haapala, 2017: Sea-ice evaluation of NEMO-Nordic 1.0 : a NEMO-LIM3.6-based ocean-sea-ice model setup for the North Sea and Baltic Sea., Geoscientific Model Development, 10, 8, 3105–3123.

Penduff, T. et al. Chaotic variability of ocean heat content: climate-relevant features and observational
1965   implications. Oceanography, **31**, 63–71 (2018)

Perugini L, et al (2017) Biophysical effects on temperature and precipitation due to land cover change. Environ Res Lett 12: 053002. doi: 10.1088/1748-9326/aa6b3f

Pielke Sr RA, et al (2011) Land use/land cover changes and climate: modeling analysis and observational
1970   evidence. WIREs Clim Change 2: 828-850. doi: 10.1002/wcc.144

Placke, M., Meier, H. E. M., and T. Neumann, 2020: Sensitivity of the Baltic Sea overturning circulation to long-term atmospheric and hydrological changes. Journal of Geophysical Research – Oceans, under review.

Prentice, IC., Bondeau, A., Cramer, W., Harrison, SP., Hickler, T., Lucht, W., Sitch, S., Smith, B., & Sykes, MT. (2007). Dynamic global vegetation modelling: quantifying terrestrial ecosystem responses to large-scale
1975   environmental change. In JG. Canadell, DE. Pataki, & LF. Pitelka (Eds.), *Terrestrial Ecosystems in a Changing*

World (pp. 175 - 192). Springer.

Primo, C., Kelemen, F. D., Feldmann, H., Akhtar, N., and Ahrens, B (2019).: A regional atmosphere–ocean climate system model (CCLMv5.0clm7-NEMOv3.3-NEMOv3.6) over Europe including three marginal seas: on its stability and performance, Geosci. Model Dev., 12, 5077–5095, https://doi.org/10.5194/gmd-12-5077-2019.

Qiao, F., Yuan, Y., Yang, Y., Zheng, Q., Xia, C., Ma, J., 2004. Wave-induced mixing in the upper ocean: Distribution and application to a global ocean circulation model. Geophysical Research Letters 31.

Qiao, W., Wu, L., Song, J., Li, X., Qiao, F., & Rutgersson, A. (2021). Momentum flux balance at the air-sea interface. Journal of Geophysical Research: Oceans, e2020JC016563.

Radtke, H., Brunnabend, S.-E., Gräwe, U., and Meier, H. E. M. (2020): Investigating interdecadal salinity changes in the Baltic Sea in a 1850–2008 hindcast simulation, Clim. Past, 16, 1617–1642, https://doi.org/10.5194/cp-16-1617-2020.

Räisänen, Jouni & Hansson, Ulf & Ullerstig, A. & Döscher, Ralf & Graham, L. & Jones, C. & Meier, H.E.M. & Samuelsson, P. & Willén, Ulrika. (2004). European climate in the late twenty-first century: Regional simulations with two driving global models and two forcing scenarios, Climate Dynamics, 22, 13-31, 10.1007/s00382-003-0365-x.

Ratnam, J. V., F. Giorgi, A. Kaginalkar & S. Cozzini (2009): Simulation of the Indian monsoon using the RegCM3-ROMS regional coupled model. Clim. Dyn., 33:119-139.

Reckermann, M., Aigars, J., Akhtar, N., Bełdowski, J., Pons-Seres de Brauwer, J., Cronin, T., Czub, M., Dähne, M., Eero, M., Hyttiäinen, K., Jalkanen,J.-P., Kiessling, A., Kjellström, E., Guo Larsén, X., McCrackin, M., Meier, M., Oberbeckmann, S., Omstedt, A., Parnell, K., Poska, A., Saarinen, J., Soomere, T., Szymczycha, B., Undeman, E., Wörman,A., Zorita, E., Multiple drivers of environmental changes and their interactions in the Baltic Sea region, ESD Discussions,

Roeckner, E., Bäuml, G., Bonaventura, L., Brokopf, R., Esch, M., Giorgetta, M., et al. (2003). The atmospheric general circulation model ECHAM 5. PART I: Model description. Max Planck Institute for Meteor. Rep. 349, MPI for Meteorology, Hamburg, Germany

Rousi, E.; Rust, H.W.; Ulbrich, U.; Anagnostopoulou, C. Implications of Winter NAO Flavors on Present and Future European Climate. *Climate* **2020**, *8*, 13, https://doi.org/10.3390/cli8010013

Rousset, C., Vancoppenolle, M., Madec, G., Fichefet, T., Flavoni, S., Barthélemy, A., Benshila, R., Chanut, J., Levy, C., Masson, S., and Vivier, F.: The Louvain-La-Neuve sea ice model LIM3.6: global and regional capabilities, Geosci. Model Dev., 8, 2991–3005, https://doi.org/10.5194/gmd-8-2991-2015, 2015

Rutgersson, A., Nilsson, E., Kumar, R., 2012. Introducing surface waves in a coupled wave-atmosphere regional climate model: Impact on atmospheric mixing length. Journal of Geophysical Research: Oceans 117.

Rutgersson, A., Kjellström, E., Haapal, J., Stendel, M., Danilovitch, I., Drews, M., Jylhä, K., Kujala, P., Guo Larsén, X., Halsnæs, K., Lehtonen, I., Luomaranta, A., Nilsson, E., Olsson, T., Särkkä, J., Tuomi, L., Wasmund, N., (2021), Natural hazards and extreme events in the Baltic Sea region, ESD Discussion

Samulelsson P, et al (2011) The Rossby Centre regional climate model RCA3: model description and performance. Tellus 63A: 4-23. doi: 10.1111/j.1600-0870.2010.00478.x

Saraiva S., H. E. M. Meier, Andersson, H., Höglund, A., Dieterich, C., Hordoir, R., and Eilola, K. (2019a): Baltic Sea ecosystem response to various nutrient load scenarios in present and future climates. Climate Dynamics, 52: 3369, https://doi.org/10.1007/s00382-018-4330-0.

Saraiva S., H. E. M. Meier, Helén Andersson, Anders Höglund, Christian Dieterich, Matthias Gröger, Robinson Hordoir, and Kari Eilola, (2019b): Uncertainties in projections of the Baltic Sea ecosystem driven by an ensemble of global climate models. Frontiers in Earth Science, 6:244, https://doi.org/10.3389/feart.2018.00244

Sato, H., Itoh, A., and Kohyama, T. 2007. SEIB-DGVM: A new Dynamic Global Vegetation Model using a spatially explicit individual-based approach, Ecol. Model., 200, 279–307.

Scaife, A.A.; Folland, C.K.; Alexander, L.V.; Moberg, A., Knight, J.R. (2008), European climate extremes and the North Atlantic Oscillation. J. Clim.,, 21, 72–83, https://doi.org/10.1175/2007JCLI1631.1

Schrum C., 2001: Regionalization of climate change for the North Sea and Baltic Sea, Climate Research 18 (1-2), 31-37

Schrum, C. 1997: A coupled ice-ocean model for the North Sea and the Baltic Sea. Sensitivity of North Sea, Baltic Sea and Black Sea to anthropogenic and climatic changes, E. Özsoy and A. Mikaelyna (eds.), Sensitivity of North Sea, Baltic Sea and Black Sea to anthropogenic and climatic changes, Nato ASI Ser., Kluwer Academic Publishers, 311-325.

Schrum, C. and Backhaus, J. 0. 1999: Sensitivity of atmosphere-ocean heat exchange and heat content in North Sea and Baltic Sea. A comparative assessment. Tellus, 51A, 526-549.

Schrum C., F. Janssen, 2002: Decadal variability in Baltic Sea ice development analysis of model results and observations, Proceeding of Fourth Workshop on Baltic Sea lce Climate, SMHI, 49

Schrum C. , Hübner U. , Jacob D. , Podzun R (2003),. A coupled atmosphere/ice/ocean model for the North Sea and the Baltic Sea. Clim. Dynam. 2003; 21(2): 131–151.

Schrum, C. (2017): Regional climate modeling and air-sea coupling. Climate Science: Oxford Research Encyclopedias, 2017. doi:10.1093/acrefore/9780190228620.013.3.

Sein, D.V., Koldunov, N.V., Pinto, J.G., Cabos, W. (2014): Sensitivity of simulated regional Arctic climate to the choice of coupled model domain. Tellus A, 66, 23966. doi:10.3402/tellusa.v66.23966.

Sein, D. V., Mikolajewicz, U., Gröger, M., Fast, I., Cabos, W., Pinto, J. G., et al. (2015). Regionally coupled atmosphere-ocean-sea ice-marine biogeochemistry model ROM: 1. description and validation. *J. Adv. Model. Earth Syst.* 7, 268–304. doi: 10.1002/2014ms000357

Sein, D.V, Gröger, M., Cabos, W., Alvarez, F., Hagemann, S., de la Vara, A., Pinto, J.G., Izquierdo, A., Koldunov, N.V., Dvornikov, A. Y., Limareva, N., Martinez, B., Jacob, D. (2020a), Regionally coupled atmosphere - ocean - marine biogeochemistry model ROM: 2. Studying the climate change signal in the North Atlantic and Europe *J. Adv. Model. Earth Syst.*, https://doi.org/10.1029/2019MS001646.

Sein, D.V., Dvornikov, A. Y., Martyanov, S., Carbos-Narvaez, W. D., Ryabchenko, V., Gröger, M., Kumar, P., Impact of the Indian Ocean temperature - phytoplankton feedback on simulated South Asia climate, J. Adv. Model. Earth Syst., submitted.

Senatore, A., Mendicino, G., Gochis, D. J., Yu, W., Yates, D. N., and Kunstmann, H. (2015). Fully coupled atmosphere-hydrology simulations for the central mediterranean: Impact of enhanced hydrological parameterization for short and long time scales. J. Adv. Model. Earth Syst. 7, 1693–1715. doi: 10.1002/2015ms000510

Sevault, F., Somot, S., Alias, A., Dubois, C., Lebeaupin-Brossier, C., Nabat, P., et al. (2014). A fully coupled mediterranean regional climate system model: design and evaluation of the ocean component for the 1980-2012 period. Tellus A 66, 23967. doi: 10.3402/tellusa.v66.23967

2075   Shrestha, P., Sulis, M., Masbou, M., Kollet, S., and Simmer, C. (2014). A scale-consistent terrestrial systems modeling platform based on COSMO, CLM, and ParFlow. *Mon. Weather Rev.* 142, 3466–3483. doi: 10.1175/mwr-d-14-00029.1

2080   Sieck, K. and Jacob, D. (2016), Influence of the boundary forcing on the internal variability of a regional climate model.Amer. J. Clim. Chang.2016,5, 373–382

Sitz, L. E., Sante, F. D., Farneti, R., Fuentes-Franco, R., Coppola, E., Mariotti, L., et al. (2017). Description and evaluation of the earth system regional climate model (Reg CM-ES). *J. Adv. Model. Earth Syst.* 9, 1863–1886. doi: 10.1002/2017ms000933

2085

Smith B, Prentice IC, Sykes MT (2001) Representation of vegetation dynamics in the modelling of terrestrial ecosystems: comparing two contrasting approaches within European climate space. Global Ecol Biogeogr 10: 621-637

Smith B, Samulelsson P, Wramneby A, Rummukainen M (2010) A model of the coupled dynamics of climate, 2090   vegetation and terrestrial ecosystem biogeochemistry for regional applications. Tellus 63A: 87-106. doi: 10.1111/j.1600-0870.2010.00477.x

Smith B, Wårlind D, Arneth A, Hickler T, Leadley P, Siltberg J, Zaehle S (2014) Implications of incorporating N cycling and N limitations on primary production in an individual-based dynamic vegetation model. Biogeosciences 11: 2027-2054. doi: 10.5194/bg-11-2027-2014

2095   Smith, E. T., & Sheridan, S. C. (2020). Where do cold air outbreaks occur, and how have they changed over time? *Geophysical Research Letters*, 47, e2020GL086983. https://doi.org/10.1029/2020GL086983

Somot, S., Sevault, F., Déque, M., & Crépon, M. (2008): 21st century climate change scenario for the Mediterranean using a coupled atmosphere ocean regional climate model. Global and Planetary Change, 63, 2100   112–126.

Soto-Navarro, J., Jordá, G., Amores, A. *et al.* (2020), Evolution of Mediterranean Sea water properties under climate change scenarios in the Med-CORDEX ensemble. *Clim Dyn* **54,** 2135–2165. https://doi.org/10.1007/s00382-019-05105-4

2105

Squire, V.A., 2018. A fresh look at how ocean waves and sea ice interact. Philosophical Transactions of the Royal Society A: Mathematical, Physical and Engineering Sciences 376. doi:10.1098/rsta.2017.0342.

Staneva, J., Alari, V., Breivik, Ø., Bidlot, J.R., Mogensen, K., 2017. Effects of wave-induced forcing on a 2110   circulation model of the north sea. Ocean Dynamics 67, 81–101.

Staneva, J., Wahle, K., Günther, H., Stanev, E., 2016. Coupling of wave and circulation models in coastal– ocean predicting systems: a case study for the german bight. Ocean Science 12, 797–806.

2115   Stokes, G.G., 1880. On the theory of oscillatory waves. Transactions of the Cambridge Philosophical Society

Strandberg, G. et al., (2015): CORDEX scenarios for Europe from the Rossby Centre regional climate model RCA4. SMHI Meteorology and Climatology Rep. 116, 84 pp., https://www.smhi.se/polopoly_fs/1.90275!/Menu/general/extGroup/attachmentColHold/mainCol1/file/ 2120   RMK_116.pdf.

Strandberg, G., and Coauthors, 2014: Regional climate model simulations for Europe at 6 and 0.2 k BP:Sensitivity to changes in anthropogenic deforestation. Climate Past, 10, 661–680, https://doi.org/10.5194/cp-10-661-2014.

Stevens, B., Fiedler, S., Kinne, S., Peters, K., Rast, S., Müsse, J., Smith, S. J., and Mauritsen, T., (2017), 2125   MACv2-SP: a parameterization of anthropogenic aerosol optical properties and an associated Twomey effect for use in CMIP6, Geosci. Model Dev., 10, 433–452, https://doi.org/10.5194/gmd-10-433-2017, 2017

Strandberg G, Kjellström E (2019) Climate impacts from afforestation and deforestation in Europe. Earth Interact 23: 1-27. doi: 10.1175/EI-D-17-0033.1

Stuecker, M.F., Bitz, C.M., Armour, K.C. et al. Polar amplification dominated by local forcing and feedbacks. Nature Clim Change 8, 1076–1081 (2018). https://doi.org/10.1038/s41558-018-0339-y

Suzuki, N., Fox-Kemper, B., 2016. Understanding stokes forces in the wave-averaged equations. Journal of Geophysical Research: Oceans 121, 3579–3596.

Tang, J., Yurova, A. Y., Schurgers, G., Miller, P. A., Olin, S.,Smith, B., Siewert, M. B., Olefeldt, D., Pilesjö, P., and Poska,A.: Drivers of dissolved organic carbon export in a subarctic catchment: Importance of microbial decomposition, sorption-desorption, peatland and lateral flow, Sci. Total Environ., 622–623, 260–274, https://doi.org/10.1016/j.scitotenv.2017.11.252,2018.

Taylor, Karl E. and Stouffer, Ronald J. and Meehl, Gerald A. 2012. An Overview of CMIP5 and the Experiment Design, B Am Meteorol Soc, 93, 4, 485-498, 10.1175/BAMS-D-11-00094.1

Teichmann, C.; Bülow, K.; Otto, J.; Pfeifer, S.; Rechid, D.; Sieck, K.; Jacob, D. (2018), Avoiding Extremes: Benefits of Staying below +1.5 °C Compared to +2.0 °C and +3.0 °C Global Warming. Atmosphere, 9, 115, DOI: 10.3390/atmos9040115

Thurow, F. (1997). Estimation of the total fish biomass in the Baltic Sea during the 20th century. ICES J. Mar. Sci. 54, 444–461. doi: 10.1006/jmsc.1996.0195

Tian T. , Boberg F. , Bssing Christensen O. , Hesselbjerg Christensen J. , She J. , co-authors (2013) . Resolved complex coastlines and land–sea contrasts in a high-resolution regional climate model: a comparative study using prescribed and modelled SSTs. Tellus A. 2013; 65: 19951. DOI: 10.3402/tellusa.v65i0.19951

Uppala, S.M., KÅllberg, P.W., Simmons, A.J., Andrae, U., Bechtold, V.D.C., Fiorino, M., Gibson, J.K., Haseler, J., Hernandez, A., Kelly, G.A., Li, X., Onogi, K., Saarinen, S., Sokka, N., Allan, R.P., Andersson, E., Arpe, K., Balmaseda, M.A., Beljaars, A.C.M., Berg, L.V.D., Bidlot, J., Bormann, N., Caires, S., Chevallier, F., Dethof, A., Dragosavac, M., Fisher, M., Fuentes, M., Hagemann, S., Hólm, E., Hoskins, B.J., Isaksen, L., Janssen, P.A.E.M., Jenne, R., Mcnally, A.P., Mahfouf, J.-F., Morcrette, J.-J., Rayner, N.A., Saunders, R.W., Simon, P., Sterl, A., Trenberth, K.E., Untch, A., Vasiljevic, D., Viterbo, P. and Woollen, J. (2005), The ERA-40 re-analysis. Q.J.R. Meteorol. Soc., 131: 2961-3012. doi:10.1256/qj.04.176

Van Pham, T., Brauch, J., Dieterich, C., Früh, B., Ahrens, B. (2014): New coupled atmosphere-ocean-ice system COSMO-CLM/NEMO: Assessing air temperature sensitivity over the North and Baltic Seas. Oceanologia, 56, 167–189. doi:10.5697/oc.56-2.167.

Vancoppenolle, M., Fichefet, T., Goosse, H., Bouillon, S., Madec,G., and Maqueda, M. A.: Simulating the mass balance and salin-ity of Arctic and Antarctic sea ice: I. Model description and val-idation, Ocean Model., 27, 33–53, 2009a

Valcke, S., Craig, T., and Coquart, L.: OASIS3-MCT User Guide,OASIS3-MCT 3.0, Tech. Rep. 1875, CERFACS/CNRS SUCURA, Toulouse, France, 201

Väli, G., Meier, H. E. M., and Elken, J. (2013). Simulated halocline variability in the Baltic Sea and its impact on hypoxia during 1961-2007. J. Geophys. Res. Oceans 118, 6982–7000. doi: 10.1002/2013jc009192

Vidale, P.L., Lüthi, D., Frei, C., Seneviratne, S.I., Schär, C. (2003): Predictability and uncertainty in a regional climate model, J Geophys Res 108 (D18), 4586. doi:10.1029/2002JD002810

Vogel, M. M., Orth, R., Cheruy, F., Hagemann, S., Lorenz, R., van den Hurk, B. J. J. M., and Seneviratne, S. I. (2017), Regional amplification of projected changes in extreme temperatures strongly controlled by soil moisture-temperature feedbacks, Geophys. Res. Lett., 44, 1511– 1519, doi:10.1002/2016GL071235

von Storch, H., H. Langenberg, and F. Feser, 2000: A Spectral Nudging Technique for Dynamical Downscaling Purposes. *Mon. Wea. Rev.*, **128**, 3664–3673, https://doi.org/10.1175/1520-0493(2000)128<3664:ASNTFD>2.0.CO;2

Wahle, K., Staneva, J., Koch, W., Fenoglio-Marc, L., Ho-Hagemann, H., Stanev, E.V., 2017. An atmosphere–wave regional coupled model: improving predictions of wave heights and surface winds in the southern north sea. Ocean Science 13, 289–301.

Wang,S., Dieterich,C., Döscher, R., Höglund,A., Hordoir, R., Meier, H. E. M., Samuelsson, P., and Schimanke, S (2015), Development and evaluation of a new regional coupled atmosphere–ocean model in the North Sea and Baltic Sea, Tellus A: Dynamic Meteorology and Oceanography, 67:1, DOI: 10.3402/tellusa.v67.24284.

Warner, J. C., Sherwood, C. R., Signell, R. P., Harris, C. K., and Arango, H. G. (2008): Development of a three-dimensional, regional, coupled wave, current, and sediment-transport model, Comput. Geosci., 34, 1284–1306.

Warner, J. C., Ganju, N. K., Sherwood, C. R., Tarandeep, K., Aretxabaleta, A., He, R., Zambon, J., and Kumar, N.: Coupled-Ocean-Atmosphere-Wave-Sediment Transport (COAWST) Modeling System(201): U.S. Geological Survey Software Release, 23 April 2019, https://doi.org/10.5066/P9NQUAOW.

Wei, J., Malanotte-Rizzoli, P., Eltahir, E. A. B., Xue, P., & Xu, D. (2014): Coupling of a regional atmospheric model (RegCM3) and a regional oceanic model (FVCOM) over the maritime continent. Climate Dynamics, 43, 1575–1594

Weisse, R., Heyen, H. & von Storch, H. Sensitivity of a regional atmospheric model to a sea statedependent roughness and the need for ensemble calculations. *Monthly Weather Rev.* **128**, 3631–3642 (2000)

Weisse, R.; Feser, F. (2003), Evaluation of a method to reduce uncertainty in wind hindcasts performed with regional atmosphere models.Coastal Eng.,,48, 211–225

Wiese A, Staneva J, Ho-Hagemann HTM, Grayek S, Koch W and Schrum C (2020) Internal Model Variability of Ensemble Simulations With a Regional Coupled Wave-Atmosphere Model GCOAST. *Front. Mar. Sci.* 7:596843. doi: 10.3389/fmars.2020.596843

Wilcke, R.A.I. and Bärring, L., (2016): Selecting regional climate scenarios for impact modelling studies. Environmental Modelling & Software 78, 191-201 http://dx.doi.org/10.1016/j.envsoft.2016.01.002

Winckler J, Reick CH, Bright RM, Pongratz J (2019) Importance of surface roughness for the local biogeophysical effects of deforestation. J Geophys Res 124: 8605-8616. doi: 10.1029/2018JD030127

Wramneby A, Smith B, Samuelsson P (2010) Hot spots of vegetation-climate feedbacks under future greenhouse forcing in Europe. J Geophys Res 115: D21119. doi: 10.1029/2010JD014307

Wu, L., Breivik, Ø., Rutgersson, A., 2019a. Ocean-wave-atmosphere interaction processes in a fully coupled modelling system. Journal of Advances in Modeling Earth Systems, doi:10.1029/2019MS001761.

Wu, L., Hristov, T., Rutgersson, A., 2018. Vertical profiles of wave-coherent momentum flux and velocity variances in the marine atmospheric boundary layer. Journal of Physical Oceanography 48, 625–641.

Wu, L., Rutgersson, A., Nilsson, E., 2017a. Atmospheric boundary layer turbulence closure scheme for wind-

following swell conditions. Journal of the Atmospheric Sciences 74, 2363–2382.

2225

Wu, L., Rutgersson, A., Sahlée, E., Guo Larsén, X., 2016. Swell impact on wind stress and atmospheric mixing in a regional coupled atmosphere-wave model. Journal of Geophysical Research: Oceans 121, 4633–4648.

Wu, L., Rutgersson, A., Sahlée, E., Larsén, X.G., 2015. The impact of waves and sea spray on modelling storm
2230   track and development. Tellus A: Dynamic Meteorology and Oceanography 67, 27967.

Wu, L., Sproson, D., Sahlée, E., Rutgersson, A., 2017b. Surface wave impact when simulating midlatitude storm development. Journal of Atmospheric and Oceanic Technology 34, 233–248.

2235   Wu, L., Staneva, J., Breivik, Ø., Rutgersson, A., Nurser, A.G., Clementi, E., Madec, G., 2019b. Wave effects on coastal upwelling and water level. Ocean Modelling , 101405.

Wyser, K., van Noije, T., Yang, S., von Hardenberg, J., O'Donnell, D., and Döscher, R.: On the increased climate sensitivity in the EC-Earth model from CMIP5 to CMIP6, Geosci. Model Dev.
2240   https://doi.org/10.5194/gmd-2019-282

Wyser, K., Kjellström, E., Königk, T., Martins, H. and Doescher, R., 2020b. Warmer climate projections in CMIP6: the role of changes in the greenhouse gas concentrations from CMIP5 to CMIP6. Environ. Res. Lett., in press, DOI: 10.1088/1748-9326/ab81c2

2245   Xie, S.P. and Philander, S.G.H. (1994): A coupled ocean-atmosphere model of relevance to the ITCZ in the eastern Pacific. Tellus, 46A:340–350

Zhang W, Jansson C, Miller PA, Smith B, Samuelsson P (2014) Biogeophysical feedbacks enhance the Arctic terrestrial carbon sink in regional Earth system dynamics. Biogeosciences 11: 5503-5519. doi: 10.5194/bg-11-5503-2014

2250   Zhang W, Miller PA, Jansson C, Samuelsson P, Mao J, Smith B (2018) Self-amplifying feedbacks accelerate greening and warming of the Arctic. Geophys Res Lett 45: 7102-7111. doi: 10.1029/2018GL077830

Zhang W, Döscher, R., Koenigk, T., P. A. Miller, Jansson, C., Samuelsson, P., Wu, M. & B. Smith (2020) The Interplay of Recent Vegetation and Sea Ice Dynamics—Results From a Regional Earth System Model Over the Arctic. Geophys Res Lett 47, 6,: e2019GL085982

2255

Zhao, D., Toba, Y., Sugioka, K.i., Komori, S., 2006. New sea spray generation function for spume droplets. Journal of Geophysical Research: Oceans 111.

Zhao, X., Shen, H.H., Cheng, S., 2015. Modeling ocean wave propagation under sea ice covers. Acta Mechanica
2260   Sinica/Lixue Xuebao 31, 1–15. doi:10.1007/s10409-015-0017-5.